

USDA-FOREST SERVICE

Index
File No. X-15

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or Survey No. Sec 34 Cor. No. C 1/4

T 3S R. 31E

R.D. Ukiah County Umatilla

Merid. Willamette

N.F. Umatilla State Oregon

CORNER DIAGRAM

T3S R31E
C 1/4 . S34



DESCRIBE CORNER MONUMENT FOUND

None.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None.

PHOTO IDENTIFICATION DATA

Photo No. _____
Filed At. _____
Object Ident. _____
Ident. By _____
Signature

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Road #5420 to road #5412-100, then West on road #5412-100 approx. 2.1 miles to road fork South through gate, through gate South 0.25 miles to CN 1/16 then South along fence 1,300 ft and East of fence 80 ft to corner in thick timber.

PLANE COORDINATE POSITION DATA

State _____ Zone _____
X _____
Y _____
Estab. By _____
Agency

Signature Title Division Headquarters Date

William R. Wells

PLS 1106

October 25, 1982

7100-52-(3.68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set ~~2~~ 1 1/2" brass cap on 2 1/2" x 30" l. pipe 24" in ground with mound of earth.
 Set steel fence post, with 54-2 & 9 signs attached, North of corner. Cap marked:

T3S R31E
 C 1/4 . S34
 1982
 PLS 1106

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

A 10" dia Fir bears N61 1/2° W 13.3 ft dist marked: C 1/2 S34 BT.

A 9" dia Fir bears S 15 1/2° E 29.3 ft dist marked: C 1/2 S34 BT.

Blaze faces and 6" bands around bearing trees are painted red. Tagged trees with 54-3 and 9 signs. BTs have a lower blaze, scribed BT, with brass washer stamped PLS 1106 nailed flush.

Work Done By W.R. Wells Title Surveyor Date 10/25/82 State Registration No. PLS 1106
or Agency

Certified Cor. Record Prepared? Yes No Filed At: Umatilla County Surveyor Office Date _____

REMARKS

Witnessed by: R. D. English PC
 D. L. Kaufman PLS