


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

X-17

History of original corner establishment: Corner originally established by George S. Pershin, U.S. Deputy Surveyor, under Contract No. 319, dated March 26, 1879. The original notes state that at the corner a Pine Post was set on nearly level ground from which:



A 20" dia Pine bears S40°E 18 lk dist.
A 26" dia Pine bears West 167 lk dist.

Remonumentation was done in 1978 by BLM, see sheet 2 for history of BLM restoration.

Description of corner evidence found:

3" brass cap on 2 1/2" l. pipe in mound of stones, from which:

A 37" dia Ponderosa Pine bears S39°E 11.9 ft dist tagged N40°W 18 lk dist (old BT, open blaze).
A 28" dia Ponderosa Pine bears N87°W 190.8 ft dist tagged S87°E 289 lk dist - recent BT.
A fallen Pine Snag bears West 108+ ft dist (old BT nearly deteriorated).


Description of monument and accessories I established to perpetuate the original location of this corner:

Blaze faces and 6" bands around trees are painted red. Tagged trees with 54-3 & 4 signs where needed. Set steel fence post with 54-4 sign attached, South of corner. Used steel tape and magnetic compass 19 3/4° East declination. Measured to center of BTs.

Corner monumented on October 6, 1982.
maintained

Standard BLM. Cap marked:

Witnessed by: Leslie E. Wilson



REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of... County Surveyor... County of... Umatilla
Oregon
State of... I hereby certify that the within instrument was filed in this office
for record on the 15th day of Decem. 1982
Darius H. Brown by Betty L. Shalt
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY
Umatilla County Surveyor
Date _____
Rec'd Ly _____
No. 82-138-B

History of 1978 Remonumentation - (From BLM Field Notes)

The 1/4 sec. cor. of secs. 34 and 35, determined at record bearing and distance from the remains of the original bearing trees:

A pine, 34 ins. diam., bears S. 40° E., 18 lks. dist., with scribe marks 1/4 S BT visible on open blaze.

A root hole, bears West, 167 lks. dist., with a down and decayed pine alongside, size indeterminate, no marks visible.

At the corner point

Set an iron post, 28 ins. long, 2 1/2 ins. diam., 20 ins. in the ground, to solid rock, and in a mound of stone, 3 ft. base, to top, with brass cap marked:

T3S R31E
1/4
S34 | S35
1978

from which a new bearing tree

A ponderosa pine, 27 ins. diam., bears N. 87° W., 289 lks dist., mkd. 1/4 S34 BT.

RECEIVED BY
Umatilla County Surveyor
Date _____
Rec'd by _____
No. 82-138-B