


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

X-21

History of original corner establishment: Corner was originally established by George S. Pershin, U.S. Deputy Surveyor, under Contract No. 319, dated March 26, 1879. The original notes state that at the corner a 12" x 10" x 8" basalt stone was set on SE face, from which:



A 5" dia Pine bears N70°E 49 lks dist.
A 20" dia Pine bears N65°W 23 lks dist.

Corner was remonumented in 1978 by BLM, see sheet 2 for history of BLM remonumentation.

Description of corner evidence found:

3" brass cap on 2 1/2" I. pipe protruding 12" out of ground in mound of stone from which:


A 22" dia Pine Stump bears N61°W 17.3 ft dist tagged S61°E 17.31 ft dist-(old BT) visible scribing.
A 12" dia Red Fir bears S52½°W 33.7 ft dist tagged N32½°E 51 lk dist - (recent blaze).
A 14" dia Tamarack bears S82°E 19.9 ft dist tagged N80°W 23½ lk dist - (recent blaze).

Description of monument and accessories I established to perpetuate the original location of this corner:

Set steel fence post with 54-2 and 4 signs attached South of corner.
Blaze faces and 6" band around bearing trees are painted red. Tagged bearing trees with 54-3 and 4 signs.
Used steel tape and magnetic compass 19 3/4° East declination. Measured to center of BTs.

Corner was maintained on October 4, 1982.

Cap is standard BLM. Cap marked:



REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of..... County Surveyor..... County of..... Umatilla
State of..... Oregon....., I hereby certify that the within instrument was filed in this office
for record on the 15th day of December, 1982
David H. Krumbein (COUNTY OFFICIAL) *Betty G. Shatt* (DEPUTY)

RECEIVED BY
Umatilla County Surveyor
Date _____
Rec'd - y _____
No. 82-137-B

History of 1978 BLM Remonumentation - (From BLM Field Notes)

The 1/4 sec. cor. of secs. 35 and 36, monumented with the original basalt stone, 12 x 10 x 8 ins., firmly set 6 ins. in the ground, and in a mound of stone, 3 ft. base, 1 ft. high, mkd. 1/4 on W. face, from which the remains of an original bearing tree:

A sawed Pine Stump, 22 ins. diam., bears N. 53° W., 23 lks. dist., with scribe marks S BT visible on open blaze. (Record, N. 65° W.)

At the corner point

Set an iron post, 28 ins. long, 2½ ins. diam., 22 ins. in the ground, and in a mound of stone, 3 ft. base, to top, with brass cap marked:

T3S R31E
1/4
S35 | S36
1978

from which new bearing trees

A Larch, 13 ins. diam., bears S. 80° E., 23½ lks. dist., mkd. ¼ S36 BT.

A Fir, 10 ins. diam., bears S. 52½° W., 51 lks. dist., mkd. ¼ S35 BT.

Deposit corner stone alongside iron post.

RECEIVED BY

Umatilla County Surveyor

Date _____

Rec'd by _____

No. 82-135-B