

Index  
File No. Y-13

**CORNER RECORD (SEARCH)**

(Ref. FSM 7151.4)

Tract or Survey No. Sec 34 Cor. No. S 1/16

T 3S R. 31E R.D. Ukiah County Umatilla  
Merid. Willamette N.F. Umatilla State Oregon

**CORNER DIAGRAM**

T3S R31E  
S 1/16  
S33 | S34



**DESCRIBE CORNER MONUMENT FOUND**

None.

**DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND.**

None.

**PHOTO IDENTIFICATION DATA**

Photo No. \_\_\_\_\_  
Filed At. \_\_\_\_\_  
Object Ident. \_\_\_\_\_  
Ident. By \_\_\_\_\_  
*Signature*

**PLANE COORDINATE POSITION DATA**

State \_\_\_\_\_ Zone \_\_\_\_\_  
X \_\_\_\_\_  
Y \_\_\_\_\_  
Estab. By \_\_\_\_\_  
*Agency*

**DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER**

Road #5420 to road #5412-100, then West on road #5412-100 approx. 2.1 miles to road fork South through gate, then South and West approx. 500 ft to road fork South (from gate), then along road South and West approx. 0.75 miles to faint road fork Southwest, along road approx. 500 ft then South approx. 100 ft to corner in sparce timber 14 ft North of E-W fence and 40 ft east of fence corner.

Signature

*William R. Wells*

Title

PLS 1106

Division

Headquarters

Date

October 25, 1982

7100-52 (3, 68)

**CORNER RECORD (PERPETUATION)**

**MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT**

Set 2 1/2" brass cap on 2 1/2" x 30" l. pipe 24" in ground with mound of earth.

Set steel fence posts with 54-9 sign on one and 54-2 signs on both, South and East of corner.  
Cap marked:

T3S R31E  
S 1/16  
S33 | S34  
1982  
PLS 1106

**ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE**

A 1 1/2" dia Fir bears N63°W 42.2 ft dist marked: S 1/16 S33 BT.

A 10" dia Pine bears S22°E 97.0 ft dist marked: S 1/16 S34 BT.

Blaze faces and 6" bands around bearing trees are painted red. Tagged trees with 54-3 and 9 signs. BTs have a lower blaze, scribed BT, with brass washer stamped PLS 1106 nailed flush.

Work Done By W.R. Wells Title Surveyor Date 10/25/82 State Registration No. PLS 1106  
or Agency

Certified Cor. Record Prepared? Yes  No  Filed At: Umatilla County Surveyor Office Date

**REMARKS**

Witnessed by: R.D. English PC  
D.L. Kaufman PLS