


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Z-13

History of original corner establishment: Corner originally established by George S. Pershin, U.S. Deputy Surveyor, under Contract No. 304, dated September 19, 1878. The original notes state that at the corner a 20" x 10" x 8" stone was set in mound of stone in small open glade for corner from which:



A 48" dia Pine bears N10°E 80 lk dist.
A 18" dia Pine bears N18°W 98 lk dist.

Corner was remonumented in 1978 by BLM, see sheet 2 for history of BLM remonumentation.

Description of corner evidence found:

3" brass cap on 2 1/2" l. pipe protruding 12" from ground in mound of stone from which:

A 50" dia Pine Snag bears N9°E 121.5 ft dist (down old BT).
A 20" dia Pine Stump bears N17 1/2°W 130.1 ft dist tagged S17 1/2°E 130.1 ft dist (old BT, visible scribing).
A 14" dia Pond. Pine bears N65°W 135.0 ft dist tagged S65°E 204 lk dist - recent blaze.
A 16" dia Pond. Pine bears N33 1/2°E 79.9 ft dist tagged S34°W 121 lk dist. - recent blaze.


Description of monument and accessories established to perpetuate the original location of this corner:

Blaze faces and 6" band around bearing trees are painted red. Tagged trees with 54-3 & 4 signs where needed.
Set steel fence posts with 54-2 signs on both and 54-4 sign on one East and North of corner.
Used steel tape and magnetic compass 19 3/4° East declination. Measured to center of BTs.

Corner maintained on October 21, 1982.

Cap is standard BLM. Cap marked:

Witnessed by: Leslie E. Wilson



REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of... County Surveyor County of... Umatilla
State of... Oregon I hereby certify that the within instrument was filed in this office
for record on the 15th day of December, 1982
Samuel P. Krumholz by *Billy J. Skatte*
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY
Umatilla County Surveyor
Date _____
Rec'd By _____
No. 82-138-B

History of 1978 BLM Remonumentation - (From BLM Field Notes)

The cor. of secs. 33 and 34 only, on the S. bdy. of the Tp., monumented with the original unmarked basalt stone, 20 x 10 x 8 ins., firmly set 6 ins. in the ground, and in a mound of stone, 3 ft. base, 6 ins. high, from which the remains of the original bearing trees:

A Pine Snag, 50 ins. diam., bears N. 10° E., 180 lks. dist., no marks visible.
(Record, 80 lks.)

A Sawed Pine Stump, 20 ins. diam., bears N. 18° W., 198 lks dist., with scribe marks BT visible on open blaze. (Record, 98 lks.)

at the corner point

Set an iron post, 28 ins. long, 2 1/2 ins. diam., 18 ins. in the ground, and in a mound of stone, 3 ft. base, to top, with brass cap marked:

T3S R31E
S33 | S34
T4S R31E
S2
1978

from which new bearing trees

A Ponderosa Pine, 16 ins. diam., bears N. 34° E., 121 lks. dist.,
mkd. T3S R31E S34 BT.

A Ponderosa Pine, 14 ins. diam., bears N. 65° W., 204 lks. dist.,
mkd. T3S R31E S33 BT.

Deposit corner stone alongside iron post.

RECEIVED BY

Umatilla County Surveyor

Date _____

Rec'd By _____

No. 82-138-B