


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Z-15

History of original corner establishment: Corner originally established by George S. Pershin, U.S. Deputy Surveyor, under Contract No. 304, dated September 19, 1878. The original notes state that at the corner a 17" x 12" x 5" stone was set on plateau on top of mountain for 1/4 cor., from which:



A 20" dia Pine bears N11°E 262 lk dist.

No record of restoration found in County Records.

Description of corner evidence found:

A 16" x 10" x 5" stone in mound of stone marked: 1/4

Description of monument and accessories established to perpetuate the original location of this corner:

Set 2 1/2" brass cap on 2 1/2" x 30" l. pipe 20" in ground with mound of stone from which:

A 18" dia Ponderosa Pine bears N81°W 85.5 ft dist marked: 1/4 S34 BT.

A 16" dia Ponderosa Pine bears N33 1/2°E 23.7 ft dist marked: 1/4 S34 BT.

Blaze faces and 6" band around bearing trees are painted red. Tagged trees with 54-3 & 4 signs.

New BTs have a lower blaze, scribed BT, with brass washer stamped PLS 1106 nailed flush.

Set steel fence post with 54-4 sign attached, East of corner.


Used steel tape and magnetic compass 19 3/4° East declination. Measured to center of BTs.

Buried original stone monument upside down along new monument.

Corner monumented on October 7, 1982.

Cap marked:

Witnessed by: Leslie E. Wilson



REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of... County Surveyor... County of... Umatilla

State of... Oregon... I hereby certify that the within instrument was filed in this office

for record on the 20th day of December, 1982

Carol A. Trumble (COUNTY OFFICIAL) *Betty S. Shado* (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY

Umatilla County Surveyor 798-276

Date _____

Rec'd By _____

No. 82-138-B