


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Z-16

History of original corner establishment:

None.

No record of corner establishment found in County Records.



Description of corner evidence found:

None.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 2 1/2" brass cap on 2 1/2" x 30" l. pipe 4" in ground in mound of stone, from which:

A 10" dia Ponderosa Pine bears N53°W 17.4 ft dist marked: E 1/16 S34 BT.

A 10" dia Ponderosa Pine bears N22°E 37.0 ft dist marked: E 1/16 S34 BT.

Blaze faces and 6" bands around bearing trees are painted red. Tagged trees with 54-3 & 9 signs. Each new BT has a lower blaze, scribed BT, with a brass washer stamped PLS 1106 nailed flush. Set steel fence posts with 54-2 signs on both and 54-9 sign on one, North and West of corner. Used steel tape and magnetic compass 19 3/4° East declination. Measured to center of BTs.

Corner monumented on October 20, 1982.

Cap marked:

Witnessed by: Leslie E. Wilson.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

T3S R31E
E 1/16 S34
T4S R31E
S1
1982
PLS 1106

Office of.....County Surveyor..... County of.....Umatilla

State of.....Oregon....., I hereby certify that the within instrument was filed in this office

for record on the 15th day of December, 1982

David P. Peterson by *Betty J. Shatto*
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY

Umatilla County Surveyor 790-276

Date _____

Rec'd By _____

No. 82-138-B