


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Z-17

History of original corner establishment: Corner originally established by George S. Pershin, U.S. Deputy Surveyor, under Contract No. 304, dated September 19, 1878. The original notes state that at the corner a 18" x 10" x 5" stone was set on level for corner from which:



- A 8" dia Pine bears N28°E 27 lks dist.
- A 6" dia Pine bears S20°E 41 lk dist.
- A 5" dia Pine bears S56°W 36 lk dist.
- A 6" dia Pine bears N2°W 40 lk dist.

Corner was remonumented in 1978 by BLM.

Description of corner evidence found:

3" brass cap on 2 1/2" l. pipe protruding 3" from ground in mound of stone from which:

- A Pine Stump bears N28°E 20.4 ft dist - (old BT, sawn tree alongside with visible scribing).
- A 12" dia Pine Stump bears N2°W 26.5 ft dist tagged S2°E 26.51 ft dist-(old BT, visible scribing).
- A 20" dia Pine bears S59°W 24.0 ft dist tagged N59°E 24.0 ft dist - (old BT, healed blaze).
- A 15" dia Red Fir bears N66°W 49.1 ft dist tagged S66°E 74 lk dist - recent blaze.
- A 17" dia Red Fir bears N64½°E 92.0 ft dist tagged S64½°W 140 lk dist - recent blaze.


Description of monument and accessories | established to perpetuate the original location of this corner:

Blaze faces and 6" bands around bearing trees are painted red. Tagged trees with 54-3 & 4 signs where needed. Set steel fence post with 54-4 sign attached, North of corner. Used steel tape and magnetic compass 19 3/4° East declination. Measured to center of BTs.

Corner maintained on October 7, 1982.

Standard BLM. Cap marked:

Witnessed by: Leslie E. Wilson



REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of.....County Surveyor..... County of.....Umatilla

State of.....Oregon..... I hereby certify that the within instrument was filed in this office

for record on the 15th day of December, 1982

Paul H. Rasmussen by *Betty L. Skatto*

(COUNTY OFFICIAL)

(DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY
 Umatilla County Surveyor 798-276
 Date _____
 Rec'd By _____
 No. 82-138-B