

USDA-FOREST SERVICE


Index File No. Z - 19
 T 3S R. 31E
 Merid. _____

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or Survey No. _____ Cor. No. 114
 R.D. Ukiah County Umatilla
 N.F. Umatilla State Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

Found 18"x13"x7" basalt stone firmly set marked 1/4 on North Face and + on top.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

A fir 22" in dia. bears N 05° W 21.7 feet. Some scribing visible. 54-3. A pine stump bears S35° E, 20.2 feet.

PHOTO IDENTIFICATION DATA

Photo No. _____
 Filed At. _____
 Object Ident. _____
 Ident. By _____
Signature

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Corner reached from C.C. of Section 6, 1245' to the East.

PLANE COORDINATE POSITION DATA

State _____ Zone _____
 X _____
 Y _____
 Estab. By _____
Agency

Barry B Barbow
 Signature

Title P.L.S. Division _____ Headquarters _____ Date 11/8/77 7100-52-(3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

At corner position set 2 1/2"x30" galvanized pipe with brass cap marked:
Placed pipe 26" in the ground and placed corner stone at base.
Mound of rock around.

T3S R31E
S35
1/4 ———
T4S
OR PLS 1051
1977

9

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

New B.T. Trip A fir 11" in dia. bears N75°E, 40.0 feet scribed 1/4 S35BT. Placed
54-3s and 54-4s on BT's, placed brass washer on BT blaze stamped PLS 1051.
Painted 6" red band and both blazes red. Placed 54-4 on fence post 5' east of
corner.

10

Work Done By B.B. Barbour Title P.L.S. Date 11/8/77 State Registration No. OR PLS 1051
or Agency

Certified Cor. Record Prepared? Yes No Filed At: _____ Date _____

REMARKS

Witnesses to the above corner: D.L. Landers.
S. Nelson

12

Index File No. T. R. M. Tract or Surv. No. Cor. 13