


History of original corner establishment:

Corner established in November, 1878 under GLO Contract:
Surveyor General's notes state:

"Set Pine post for 1/4 sec. cor.
A Pine 10" in dia. bears South 11 lks dist.
A Fir 5" in dia. bears N40°E, 16 lks dist."



Description of corner evidence found:

None found. A fir 12" in dia. bears N40°E, 10.6 feet partially opened with letter B visible. Old rotten stump about 7' south lying on the ground. No scribing could be found.

Description of monument and accessories established to perpetuate the original location of this corner:

At point S40°W, 10.6 feet set 2½" x 30" galvanized pipe with brass cap marked:
Set pipe 24" in the ground, with mound of stone around.
A Fir 10" in dia. bears N56°W, 14.4 feet, scribed 1/4 S36 BT.
Placed 54-3s and 54-4s and brass washer stamped PLS 1051 on BT blaze.
Painted 6" red band and both blazes red.
Placed 54-2 and 54-4 on fence post 5' west of corner.

T3S	R31E
1/4	S36
T4S	R32E
OR PLS 1051	1977

I hereby certify the above corner monument was reestablished as herein described.

Witnesses: D.L. Landers
S. Nelson

November 8, 1977
See Record Plat S6, T4S, R32E, W.M.,
as filed with the Umatilla County Surveyor.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Barry B. Barbour

OREGON
OCT. 17, 1975
BARRY B. BARBOUR
1051

Office of..... County of Umatilla
State of Oregon I hereby certify that the within instrument was filed in this office
for record on the day of 19 ..
..... by
(COUNTY OFFICIAL) (DEPUTY)