

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

E - 9
DIAGRAM

History of original corner establishment:

The original corner was established by George S. Pershin on May 26, 1882, under GLO contract No. 430, as follows:

T3S R32E
S5|S4
S8|S9
PLS 1636
1998

Descent about 350 feet, set a basalt stone, 12" x 8" x 6", 8" into the ground on east slope for corner to sections 4, 5, 8 & 9, marked with five notches on the south and four notches on the east edges, from which:

- A 8" fir bears N86°E, 36 links (23.76 feet), marked "T3S R32E S4 BT".
- A 11" fir bears S54°E, 28 links (18.48 feet), marked "T3S R32E S9 BT".
- A 16" fir bears S54°W, 45 links (29.70 feet), marked "T3S R32E S8 BT".
- A 20" pine bears N20°W, 141 links (93.06 feet), marked "T3S R32E S5 BT".

Corner evidence recovered:

The corner point is on the cut slope of a logging spur road, and the corner stone is gone. A sawn and badly decayed 22" fir stump, with scribes "BT" visible, bears S65°W, 29.7 feet. A sawn and decayed 24" Ponderosa Pine stump, four feet high, with full scribes visible on previously opened double blazes, bears N18°30'W, 93.1 feet. The bearing trees of record to the east have been destroyed by road construction.

Monument and accessories established to perpetuate the original location of this corner:

At the intersection point of record distance from the two remaining bearing tree remnants, I set a 1" x 30" iron pipe 29" into the ground. A 2 1/2" brass cap attached to the pipe is marked as shown in the diagram above, from which:

- A 16" White Fir scribed "T3S R32E S4 BT" bears N23°E, 73.6 feet.
- A 10" White Fir scribed "T3S R32E S9 BT" bears S42°30'E, 29.3 feet.
- A 13" Douglas-fir scribed "T3S R32E S8 BT" bears S41°W, 41.9 feet.
- A 17" White Fir scribed "T3S R32E S5 BT" bears N81°W, 24.0 feet.

The four new bearing trees are scribed on double blazes, have a 3/4" brass washer, marked "PLS 1636", nailed flush to the scribed "B", and have a "Bearing Object" sign nailed above the blazes and a "Witness Post" sign nailed to the back side of the tree. The original Ponderosa Pine stump also has a "Bearing Object" sign nailed to it. The original fir bearing tree stump is too decayed to nail a sign to.

I hereby certify the above corner point was perpetuated as hereon described on April 9, 1998. Magnetic declination: 18°E.



Reviews June 30, 1999

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on _____, 1998.

RECEIVED BY
Umatilla County Surveyor
Date 4-98
Rec'd By KK
No. 98-73-R