

Index CORNER RECORD (SEARCH)  
 File No. (Ref.FSM 7151.4)  
 T 3 S R 32 E R.D. N. F. John Day County Umatilla  
 Merid. Willamette N.F. Umatilla State Oregon

## CORNER DIAGRAM DESCRIBE CORNER MONUMENT FOUND

T3S R32E Not previously established.

1 S11

W-- ---

16 S14

PLS 852

1987

DESCRIBE BEARING TREES OR OTHER  
 OFFICIAL ACCESSORIES FOUND  
 Not previously set.

PHOTO  
 IDENTIFICATION

## DATA

Photo No.

Object Ident.

DESCRIBE CORNER LOCATION RELATIVE TO  
 NEAR-BY FEATURES, ALSO HOW TO REACH CORNER  
 Go south on road 54 from Birch Creek to road  
 5411. Take road 5411 to road 5411050. Take road  
 5411050 to road 5411436. Take road 5411436 to  
 gate. Go west along fence 1000' to corner.  
 The corner is about 20' south of the fence.

Signature

*David L. Hackbe*

Title

Land Surveyor

Headquarters

Pendleton, OR

Date

10-87

CORNER RECORD (PERPETUATION)

MONUMENT :DESCRIBE NEW MONUMENT SET  
OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set a 2" I.D. galvanized iron pipe 30" long with 2 1/2" brass cap 26" into the ground. Stamped the brass cap as shown on the corner diagram. Set a steel fence post 5' east of the monument with Forest Service Land Survey Monument and Property Boundary signs attached.

ACCESSORIES:DESCRIBE NEW BT,s WITNESS OBJECTS ETC. ESTABLISHED,  
OR WORK DONE TO PRESERVE EXISTING EVIDENCE

Placed a 3' diameter collar of stone around the monument. Scribed W1/16 S11 BT on a 15" White Fir which bears N 64°57'W, 36.6'. Scribed W1/16 S14 BT on a 8" White Fir which bears S54°04'W, 19.1'. The bearings are true. Each scribe is in a 24" blaze. Nailed an aluminum washer between the letters B and T on each tree. Painted a 6" red band around each tree and attached Forest Service Land Survey Monument and Bearing Tree signs.

Work Done By David L. Haddock Title Land Surveyor Date 10-87  
Certified Corner Record Prepared? Yes x No  
Filed at Pendleton, OR Date 12-3-87 State Registration No. 852

REMARKS

Index File No. J-18

T. 3 S R 32 E

M Willamette