


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. J-19

History of original corner establishment:

The original corner was established by George Pershin under G.L.O. contract 430, dated March 23, 1882. His record reads:

Set a basalt Stone 12X10X8 ins 8 ins in the ground, on level. in open glade for 1/4 Sec. Cor, marked 1/4 on N face. no trees near; raised a mound of stone in lieu of pits



Description of corner evidence found:

Found 12x10x8 stone with chisel marks in face. A 1, a / and part of a 4 were visible. The stone was not in a mound. It appeared to have been placed in an old rock jack and to have rolled off down hill when the rock jack rotted out. The proportioned point, under a newer fence, bears N48°20'E, 24.2' from the point where the original stone was found, 6.8' downhill from the old rock jack. There was a long continuous mound of stones under this newer fence. The corner was proportioned in at a point half way between the section corners which were found 1/2 mile east and west of the point. This point fell at the west end of the long stone mound and directly under the fence.

Description of monument and accessories | established to perpetuate the original location of this corner:

Set a 2" I.D. galvanized iron pipe 30" long with 2 1/2" brass cap stamped as shown in the diagram above. Set pipe 4" into the ground on the south sloping face of a large boulder which was just under the ground surface. Buried original stone alongside.

Placed a 4' diameter mound of stone around the monument and set a steel fence post 5' east of the monument with Forest Service Land Survey Monument and Property Boundary signs attached. Scribed 1/4 S11 BT on a 12" Douglas Fir which bears N79°00'E, 97.8'. Scribed 1/4 S14 BT on a 9" Ponderosa Pine which bears S38°42'E, 128.7'. The bearings are true. Each scribe is in a 24" blaze. Nailed an aluminum washer, stamped RLS 852, between the letters B and T on each tree. Painted a 6" red band around the new bearing trees and attached Forest Service Land Survey Monument and Bearing Tree signs.

I certify the above corner point was perpetuated as hereon described on October 26, 1987.

Witness: Wilma Nell Haddock

REGISTERED PROFESSIONAL LAND SURVEYOR

David L. Haddock

OREGON JULY 12, 1968 DAVID L. HADDOCK 852

Office of Surveyor... County of Umatilla... State of Oregon... I hereby certify that the within instrument was filed in this office for record on the 23 day of November, 1987... David H. Klen... (COUNTY OFFICIAL)

RECEIVED BY

Umatilla County Surveyor W.A. GPO-798-276

Date 12-87 Rec'd By [Signature] No. 87-68-B