

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


J-7

History of original corner establishment:

Original corner established on May 25, 1882 by George S. Pershin, as follows:
Set a basalt stone, 12" x 7" x 5", 8" into the ground on west slope marked 1/4 on the north face, from which:

A 20" pine bears N42°E, 24 links (15.84 feet) marked 1/4 S BT.

A 18" pine bears S45°W, 8 links (5.28 feet) marked 1/4 S BT.



Description of corner evidence found:

Found original stone, 12" x 6" x 6", set firmly in the ground and marked "1/4" on the north face, from which:

A root hole with a down 18" Ponderosa Pine lying alongside, marked "1/4 S BT" on double blazes; center of root hole bears N42°E, 19.2 feet.

A root hole with a down and decayed 16" Ponderosa Pine lying alongside, no marks remain; center of root hole bears S45°W, 5.3 feet.

Description of monument and accessories established to perpetuate the original location of this corner:

Moving the corner stone aside, I set in it's place a 1 1/2" X 30" galvanized iron pipe 24" into the ground. A 2 1/2" brass cap attached is marked as shown in the diagram. I bury the corner stone alongside the north side of the pipe. From which:

A 9" Ponderosa Pine bears S16°W, 21.3 feet scribed "1/4 S17 BT" on a single blaze.

A 19" Douglas Fir bears N50°E, 15.3 feet scribed "1/4 S8 BT" on a single blaze

Both new bearing trees have a 3/4" brass washer, marked "LS 1636", nailed flush to the lower portion of the blaze, and a "Umatilla County Bearing Object" sign nailed above the blaze.

I set a 5 foot steel fence post one foot east of the corner monument.

I hereby certify this corner position was perpetuated as hereon described on August 7, 1987. De: 20°E. Witness: Steven J. Scritchfield



Office of County Surveyor..... County of..... Umatilla
 State of... OREGON..... I hereby certify that the within instrument was filed in this office
 for record on the 20th day of Sept. 1987
 David H. Keumbria..... by..... J. Hulzen Klumbria
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

Umatilla County Surveyor
 Date 9-87
 Rec'd By [Signature]
 No. 87-50-R