

USDA-FOREST SERVICE

Index File No. R-17

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or Survey No. Sec 26 Cor. No. NW

T 3S R. 32E

R.D. Ukiah County Umatilla

Merid. Willamette

N.F. Umatilla State Oregon

CORNER DIAGRAM

T3S R32E
S22 | S23
S27 | S26



DESCRIBE CORNER MONUMENT FOUND

3" brass cap on 2 1/2" I. pipe in mound of stone.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

A 18" dia R Fir brs. N65°W51.1 ft tagg. S 64° E76 lk dist (old BT open blaze)
A 14" dia P Pine brs. S24°W56.2 ft. tagg. N24° E85 1/2 lk dist (recent BT)
A 26" dia P Pine brs. S50°E31.2 ft. tagg. N38°W47lk (old BT healed blaze)
A 31" dia P Pine brs. N86 1/2°E41.7 ft. tagg. S88°W61 lk dist (old BT healed blaze)

PHOTO IDENTIFICATION DATA

Photo No. 616140 680-296
Filed At. Umatilla Nat. Forest
Object Ident. Trees
Ident. By _____
Signature

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Pearson Creek road #54 to road #5412 then West to #5412-010 then North to road 026 then Northeast 1/2 mile then North 200 ft. to corner.

PLANE COORDINATE POSITION DATA

State _____ Zone _____
X _____
Y _____
Estab. By _____
Agency

Signature
Willie R. Welch

Title
PLS 1106

Division

Headquarters

Date
September 22, 1982

7100-52-(3,68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set steel fence post, with sign 54-4, on section line near corner.
Cap marked:

T3S R32E
S22 | S23
S27 | S26
1977

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

Painted blaze faces and a 6" band around bearing trees red.
Tagged w/54-3 & 4 signs where needed.

Work Done By W.R. Wells Title Surveyor Date 9/22/82 State Registration No. PLS 1106
or Agency

Certified Cor. Record Prepared? Yes No Filed At: Umatilla County Surveyor Office Date

REMARKS

Witnessed by : D.L. Kaufman PLS

Index File No.
R-17

T. 3S

R. 32E

M. W.M.

Tract or Surv. No.

S26

Cor. NW