


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

R-19

History of original corner establishment: Corner originally established by George S. Pershin, U.S. Deputy Surveyor, under Contract No. 430, dated May 15, 1882. The original notes state that at the corner a 17" x 10" x 5" basalt stone was set 12" in ground on level. Marked 1/4 on North face.



No BTs set.

No record of restoration found in County Records.

Description of corner evidence found:

16" x 14" x 5" basalt stone 10" in ground in small stone mound, marked 1/4 on North face.


Description of monument and accessories established to perpetuate the original location of this corner:

I set at the undisturbed corner position a 2 1/2" brass cap on 2 1/2" x 30" l. pipe 24" in ground surrounded by mound of stone. Buried original stone upside down alongside monument. Set new BTs as follows:

- A 9" Red Fir bears S52°E 19.8 ft. dist. marked 1/4 S26 BT.
A 11 1/2" Tamarack bears N31°E 26.5 ft. dist. marked 1/4 S23 BT.
Painted red 6" band around bearing trees and blaze faces. Tagged the trees with 54-3 & 4 signs. New BTS have lower blaze, scribed BT, with brass washer stamped PLS 1106 nailed flush.
Set steel fence post with 54-4 sign on section line near corner.
Used steel tape and magnetic compass 19 3/4° East declination. Measured to center of trees.

Corner monumented on September 23, 1982.

Cap marked:



Witnessed by: D.L. Kaufman PLS

REGISTERED PROFESSIONAL LAND SURVEYOR

William R. Wells

OREGON JULY 22, 1977 WILLIAM R. WELLS 1106

Office of... County Surveyor... Umatilla
State of... Oregon... I hereby certify that the within instrument was filed in this office
for record on the 13th day of November... 1982
David H. Johnson by Betty Shatto

RECEIVED BY Umatilla County Surveyor Date Rec'd by No. 82-136-B