

USDA-FOREST SERVICE

Index

File No.

S-~~14~~ 1B

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or

Survey No.

Sec 26

Cor.

No.

NW 1/16

T 3S

R. 32E

R.D.

Ukiah

County

Umatilla

Merid.

Willamette

N.F.

Umatilla

State

Oregon

CORNER DIAGRAM

T3S R32E

NW 1/16 . S26



DESCRIBE CORNER MONUMENT FOUND

None.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None.

PHOTO IDENTIFICATION DATA

Photo No.

Filed At.

Object Ident.

Ident. By

Signature

PLANE COORDINATE POSITION DATA

State Zone

X

Y

Estab. By

Agency

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER
Road #54 to road #5412, then N W on road #012 to road #016, then North on road #016 approximately 1,000 ft. then N E 500 ft. to corner at edge of timber on North edge clearing on steep North face.

Signature

Walter R. Wells

Title

PLS 1106

Division

Headquarters

Date

October 18, 1982

7100-52-(3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set 2 1/2" brass cap on 2 1/2" x 30" l. pipe 21" in ground with mound of stone.
Set steel fence posts South and West of corner, with 54-2 signs on both and
54-9 sign on one. Cap Marked:

T3S R32E
NW 1/16 . S26
1982
PLS 1106

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

A 11" dia. Red Fir bears S13°W 16.2 ft. dist. marked: NW 1/16 S26 BT.
A 15" dia. Grand Fir bears S61°E 5.5 ft. dist. marked: NW 1/16 S26 BT.
Blaze faces and 6" band around bearing trees are painted red. Tagged trees with 54-3 & 9 signs.
Each new BT has lower blaze, scribed BT, with brass washer stamped PLS 1106 nailed flush.

Work Done By: W. R. Wells Title Surveyor Date 10/18/82 State Registration No. PLS 1106
or Agency
Certified Cor. Record Prepared? Yes No Filed At: Umatilla County Surveyor Office Date

REMARKS

Witnessed by: Leslie E. Wilson

Index File No. S-14 T. 3S R. 32E M. W.M. Tract or Surv. No. Sec 26 Cor. NW 1/16