


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T-17

History of original corner establishment: Corner originally established by George S. Pershin, U.S. Deputy Surveyor, under Contract No. 430, dated May 15, 1882. The original notes state that at the corner basalt stone 12 x 8 x 7 inches was set 8" in ground on slight S.E. slope. Marked 1/4 on West face, from which:



A Pine 6" dia. bears S42° E 42 lks dist. marked 1/4 BT.
A Pine 20" dia. bears N48°W 64 lks dist. marked 1/4 BT.

Remonumentation was done in 1977 by BLM, see sheet 2 for record of BLM remonumentation.

Description of corner evidence found:

At the corner location, found 3" brass cap on 2 1/2" I. pipe in mound of stone, from which:

A 29" P. Pine bears N48°W 43.3 ft. dist. tagged S48°E 64 lk w/partially open blaze (original BT)
A 23" P. Pine bears S43°E 27.8 ft. dist. tagged N43°W-27.8 ft w/chopped out blaze (original BT)


Description of monument and accessories established to perpetuate the original location of this corner:

Set steel fence posts 3 ft. West and South and attached signs 54-2 facing North and East respectively and 54-4 sign on the West post.
Painted red the face of blazes and 6" bands around bearing trees. Tagged trees w/54-3 & 4 signs where needed.
Used steel tape and magnetic compass 19 3/4° East declination. Measured to center of BTS.

This corner maintained on September 22, 1982.

The cap is a standard 3" BLM cap marked

Witnessed by: D.L. Kaufman, PLS



REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of... County Surveyor County of... Umatilla
State of... Oregon I hereby certify that the within instrument was filed in this office
for record on the 15th day of December, 1982
David H. Fraumbein by *Betty L. Slatts*
(COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY
Umatilla County Surveyor
Date _____
Rec'd by _____
No. 82-136-R

History of 1977 BLM Remonumentation

The 1/4 sec. cor. of secs. 26 and 27, monumented with the original basalt stone, 12 x 8 x 7 ins., firmly set 8 ins. in the ground, mkd. 1/4 on N. face, from which the original bearing trees:

A Pine, 24 ins. diam., bears S. 42° E., 42 lks. dist., with fragmentary scribe marks visible on partially healed blaze.

A Pine, 33 ins. diam., bears N. 48° W., 64 lks. dist., with scribe marks 1/4 visible on partially healed blaze.

At the corner point

Set an iron post, 28 ins. long, 2½ ins. diam., 16 ins. in the ground, to solid rock, and in a mound of stone, 3 ft. base, to top, with brass cap marked:

T3S R32E
1/4
S27 S26
1977

Deposit corner stone alongside iron post.

RECEIVED BY
Umatilla County Surveyor
Date _____
Rec'd by _____
No. 82-136-B