

USDA-FOREST SERVICE


Index
File No. T-17
T. 3S R. 32E
Merid. Willamette

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or Survey No. Sec 26 Cor. No. W 1/4
R.D. Ukiah County Umatilla
N.F. Umatilla State Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

3" brass cap on 2 1/2" l. pipe in mound of stone.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES, FOUND

A 29" P. Pine bears N48° W43.3 ft. dist. tagged S48°E 64lk (old BT) partially open blaze
A 23" P. Pine bears S43°E 27.8 dist (old BT) has chopped out blaze

PHOTO IDENTIFICATION DATA

Photo No. 616140 680-297
Filed At. Umatilla National Forest
Object Ident. Trees
Ident. By _____
Signature

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Pearson Creek Road #54 to intersection of road 5412. Then West to 5412-010, then North approx. 3/8 mi. then right 500 ft. along road to Cames cabin then North 200 ft. to corner.

PLANE COORDINATE POSITION DATA

State _____ Zone _____
X _____
Y _____
Estab. By _____
Agency

Signature
William R. Wells

Title
PLS 1106

Division

Headquarters

Date
Sept. 22, 1982

7100-52-(3/68)

2

3

4

5

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set steel fence posts 3 ft. West & South of Corner and attached signs 54-2 to both posts and sign 54-4 to one post. Cap is standard BLM cap marked:

T3S R32E
1/4
S27 S26
1977

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

Painted the face of the blazes and 6" bands around bearing trees red. Tagged trees W/54-3 & 4 signs where needed.

Work Done By W. R. Wells Title Surveyor Date 9/22/82 State Registration No. PLS 1106
or Agency

Certified Cor. Record Prepared ? Yes No Filed At: Umatilla County Surveyor Office Date

REMARKS

Witnessed by: D. L. Kaufman, PLS

Index File No.

T-17

T.

3S

R.

32E

M.

W.M.

Tract or Surv. No.

S26

Cor.

W 1/4