


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

U-17

History of original corner establishment:

None.



Description of corner evidence found:

None.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set a 2 1/2" brass cap on 2 1/2" x 30" l. pipe 17" in the ground with mound of earth and stone, from which:

A 11" dia. P. Pine bears N17°W 62.6 ft dist. marked: S 1/16 S27 BT.

A 13" dia. P. Pine bears N69°E 87.4 ft dist. marked: S 1/16 S26 BT.

Painted blaze faces and 6" band around bearing trees red. Trees tagged with 54-3 & 9 signs.


Set steel fence posts North and East of corner with 54-9 sign on one and 54-2 signs on both.

Each new BT has a lower blaze scribed BT with a brass washer stamped PLS 1106 nailed flush.

Used steel tape and magnetic compass 19 3/4° East declination. Measured to center of BTs.

Corner monumented on October 18, 1982.

Cap marked:



Witnessed by: Leslie E. Wilson

**REGISTERED  
PROFESSIONAL  
LAND SURVEYOR**

*William R. Wells*

**OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106**

Office of..... County Surveyor..... County of..... Umatilla

State of..... Oregon....., I hereby certify that the within instrument was filed in this office

for record on the 15<sup>th</sup> day of December, 1982

*David H. Drumbeby* (COUNTY OFFICIAL) *Billy L. Shatto* (DEPUTY)

Form R6-7100-57 (9/71)

**RECEIVED BY**

☆ GPO—798-276

**Umatilla County Surveyor**

Date \_\_\_\_\_

Loc. No. \_\_\_\_\_

l.c. 82-136-B