

USDA-FOREST SERVICE

Index

File No. U-17

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or

Survey No.

Sec 27

Cor.

No.

S 1/16

T 3S R. 32E

R.D.

Ukaih

County

Umatilla

Merid. Willamette

N.F.

Umatilla

State

Oregon

CORNER DIAGRAM

T3S R32E

S 1/16

S27 | S26



DESCRIBE CORNER MONUMENT FOUND

None.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None.

PHOTO IDENTIFICATION DATA

Photo No. \_\_\_\_\_

Filed At. \_\_\_\_\_

Object Ident. \_\_\_\_\_

Ident. By \_\_\_\_\_

*Signature*

PLANE COORDINATE POSITION DATA

State \_\_\_\_\_ Zone \_\_\_\_\_

X \_\_\_\_\_

Y \_\_\_\_\_

Estab. By \_\_\_\_\_

*Agency*

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Road #54 to road #5412, then West to road #010, then North 1,000 ft. to road to East, along road to East 300 ft. then North 70 ft. to corner in small clearing on N W facing slope.

Signature

*Willie R. Wells*

Title

PLS 1106

Division

Headquarters

Date

October 18, 1982

7100-52-(3/68)

**CORNER RECORD (PERPETUATION)**

**MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT**

Set 2 1/2" brass cap on 2 1/2" x 30" l. pipe 17" in ground with mound of earth and stone.

Set steel fence posts North and East of corner, with a 54-9 sign on one and 54-2 signs on both. Cap marked:

T3S R32E  
S 1/16  
S27 S26  
1982  
PLS 1106

**ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE**

A 11" dia. P. Pine bears N17°W 62.6 ft. dist. marked: S 1/16 S27 BT.

A 13" dia. P. Pine bears N69°E 87.4 ft dist. marked: S 1/16 S26 BT.

Blaze faces and 6" band around bearing trees are painted red. Trees tagged with 54-3 & 9 signs. Each new BT has a lower blaze scribed BT with a brass washer stamped PLS 1106 nailed flush.

Work Done By W.R. Wells Title Surveyor Date 10/18/82 State Registration No. PLS 1106  
or Agency

Certified Cor. Record Prepared? Yes  No  Filed At: Umatilla County Surveyor Office Date

**REMARKS**

Witnessed by: Leslie E. Wilson

Index File No.  
U-17

T.

3S

R.

32E

M.

W.M.

Tract or Surv. No.

Sec 27

Cor.

S 1/16