

USDA-FOREST SERVICE

Index
File No. V-13
T 3S R. 32E
Merid. Willamette

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)
Tract or Survey No. Sec 27 Cor. No. SW Cor.
R.D. Ukiah County Umatilla
N.F. Umatilla State Oregon

CORNER DIAGRAM

T3S R32E
S28 | S27
S33 | S34



PHOTO IDENTIFICATION DATA

Photo No. _____
Filed At. _____
Object Ident. _____
Ident. By _____
Signature T

PLANE COORDINATE POSITION DATA

State _____ Zone _____
X _____
Y _____
Estab. By _____
Agency S

DESCRIBE CORNER MONUMENT FOUND

3" brass cap on 2 1/2" l. pipe protruding 12" from ground.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

- A 15" W. Fir Snag brs. S78°W 5.7 ft. dist. tagg. N70°E 9lk dist. Part. Healed blaze (~~old~~ BT)
- A 18" T. brs. N43°W 38.2 ft. dist. tagg. S38°E 58 lk dist (old BT) open blaze
- A 18" R. Fir brs. S38½°E 43.3 ft dist tagg. N38°W 66lk dist-recent blaze.
- A 13" R. Fir brs. S31°W 61.2 ft dist tagg. N32°E 93lk dist. -recent blaze.
- A 16" R. Fir brs. N50°E 96.0ft dist tagg. S49½°W 146lk dist. -recent blaze.

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Pearson Creek Road #54 to road #5412, West to road #5415, North to road #020, then East 500 ft along road, then South 100 ft to the corner.

Signature
William R. Kelly

Title
PLS 1106

Division

Headquarters

Date
September 23, 1982

7100-52-(3/68)

2

6

4

5

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set steel fence post, with 54-4 sign, on section line near corner.
Cap is standard BLM. Cap marked:

T3S R32E
S28 | S27
S33 | S34
1977

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

Painted 6" band around bearing trees and blaze faces red. Tagged trees with 54-3 & 4 signs where needed.

Work Done By W.R. Wells Title Surveyor Date 9/23/82 State Registration No. PLS 1106
or Agency

Certified Cor. Record Prepared? Yes No Filed At: Umatilla County Surveyor Office Date

REMARKS

Witnessed by: D.L. Kaufman PLS

Index File No.
V-13

T. 3S R. 32E M. W.M.

Tract or Surv. No.

S27

Cor. SW Cor.