

USDA-FOREST SERVICE

Index

File No. A-9

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or Survey No. _____ Cor. No. _____ Sec. _____


T 3 & 4 S R. 32E

R.D. Ukiah County Umatilla

Merid. W.M.

N.F. Umatilla State Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

Found 19"x10"x6" basalt stone firmly set with 4 notches on east side and 2 notches on west side.

2

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

A Tamarac 21" in dia. bears N78°E, 13.5 feet. Grown over blaze. A snag 21" in dia. bears N38°W, 65.5 feet. Scribed T3S, R32E S32 BT. 54-3 and old 54-4 on both trees.

3

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Corner is about 1150' west of main forest service road going through Granite Meadows.

4

PHOTO IDENTIFICATION DATA

Photo No. _____

Filed At. _____

Object Ident. _____

Ident. By _____

Signature _____

6

7

PLANE COORDINATE POSITION DATA

State _____ Zone _____

X _____

Y _____

Estab. By _____

Agency _____

8

Signature

Barney B. Barbour

Title

P.L.S.

Division

Headquarters

Date

10/26/77


7100-52-(3/68)

5

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

At corner position set 2 1/2"x30" galvanized pipe with brass cap marked: Placed corner stone at base of pipe and set pipe 24" in the ground with mound of stone around.



ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

New BT's: A fir 15" in dia. bears S12°E, 23.6 feet scribed T4S R32E S4 BT. A pine 11" in dia. bears S83°W 53.7 feet scribed T4S R32E S5 BT. A pine 8" in dia. bears N22°W, 36.5 feet scribed T3S R32E S32 BT. Placed 54-3s & 54-4s on all the BT's. Placed brass washer stamped PLS 1051 on foot blazes. Painted 6" red band around the BT's and painted blazes red. Placed 54-4 on fence post 3' east of corner.

Work Done By B.B. Barbour Title P.L.S. Date 10/26/77 State Registration No. OR PLS 1051

Certified Cor. Record Prepared? Yes No Filed At: _____ Date _____

REMARKS

Witnesses to the above corner: D.L. Landers
S. Nelson