


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX FILE NO. A-13

History of original corner establishment:

In 1882, under G.L.O. contract No. 451, Rufus S. Moore set basalt stone 15x12x7 ins., 10 ins. in the ground for corner to sec's. 3-4-33 & 34 marked with 3 notches on the E & W edges and raised a mound of stone alongside, pits imprac., from which: A willow 3 ins. dia. bears S50⁰W, 15 lks dist. marked T5S R33E S4 BT in clump of willow brush.




Description of corner evidence found:

At corner location found stone 15"x12"x7", 6" above the ground with 3 notches on E&W faces visible. A stone mound one foot high and 3 ft. dia. at base is along west side of corner stone. Could find no trace of willow BT.

Description of monument and accessories established to perpetuate the original location of this corner:

In place of original stone set 2 1/2"x30" galvanized pipe with brass cap stamped:

Set Pipe 22" in ground with mound of stone to cap. Buried original stone alongside.



Bearing Trees:

A Douglas Fir 15" dia. bears S34⁰E, 55.7 ft., scribed T3S R33E S3 BT.
 A Douglas Fir 27" dia. bears S78⁰W, 47.0 ft., scribed T3S R33E S4 BT.

Attached 54-3 & 54-4 signs to all BT's. Attached brass washer stamped LS1294 to foot blaze of new BT's. Painted blazes and 6" band around both BT's red. Attached 54-2 & 54-4 signs to metal post 5' west of corner.

I hereby certify the above corner monument was re-established as herein described on June 30, 1980.

Witnesses: R. Orton
 L. Huntsman
 D. Allen



Office of.....County Surveyor..... County of.....Umatilla
 State of.....Oregon....., I hereby certify that the within instrument was filed in this office for record on the.....day of.....*November*....., 19⁸⁰
David H. Huntsman..... by *Betty Shatto*
 (COUNTY OFFICIAL)..... (DEPUTY)

R-188A