


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index file No. A-9

History of original corner establishment: In 1882, under G.L.O. Contract No. 451, Rufus S. Moore, set basalt stone 15x8x5 ins. - 10 ins. in ground for cor. to secs. 4, 5, 31 and 32 with 4 notches on east and 2 notches on west sides from which a Pine 18" dia. bears N47°W, 87 lks dist. marked T2S R33E S32BT.



Description of corner evidence found:

Could find no evidence of original stone. Found 22" Ponderosa Pine with open blaze and visible scribing "T2S R33E S32BT" scribing is faint. "X" is scribed in bark on back side of BT.


Description of monument and accessories established to perpetuate the original location of this corner At Record Bearing and distance (S47°E, 87 lks = 57.42').

Set 2½"x30" Galvanized Pipe with brass cap stamped:
Set pipe 10" in ground with mound of stone to cap.

NEW BTS: A Ponderosa Pine 36" dia. bears S80°E, 75.9 ft. scribed T3S R33E S4BT.

A Ponderosa Pine 14" dia. bears S82°W, 151.1 ft. scribed T3S R33E S5 BT.

Attached 54-3 and 54-4 signs to all BTs. Attached brass washer stamped LS 1294 to foot blaze of new BTs. Painted blazes and 6" band around both BTs. red. Attached 54-2 and 54-4 signs to metal post 6' west of corner.



I hereby certify the above corner monument was reestablished as herein described on July 29, 1980.

Witnesses: R. Orton
L. Huntsman
D. Allen



Office of _____ County Surveyor _____ County of Umatilla
State of Oregon, I hereby certify that the within instrument was filed in this office for record on the _____ day of December, 1980.
David Krumbain by Betty Skatts
(COUNTY OFFICIAL) (DEPUTY)