


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. J-17

History of original corner establishment:

In 1882, under GLO Contract No. 451, Rufus S. Moore set a stone 12x8x6, from which a 40" Spruce bears N64°W, 42 lks.; an 8" Fir bears N38°E, 14 lks.; a 14" Fir bears S68°E, 36 lks.; and a 20" Fir bears S39°W, 10 lks.



Description of corner evidence found:

No corner monument found.

Bearing Trees Found:

- A 41" Spruce bears N4°W, 27.7 ft., blaze healed.
- An 18 1/2" Fir bears S68°E, 23.8 ft., blaze healed.
- A 25 1/2" Fir bears S39°W, 6.6 ft., blaze healed.

There is a discrepancy between the location of the northwest BT and what is called for in the original GLO notes. The healed mark on the northwest BT faces the corner and appears to be at the right height for the original blaze. There is no tree or remains of stump or tree at the recorded bearing and distance.

Description of monument and accessories established to perpetuate the original location of this corner:

Set 2 1/2" x 30" aluminum capped aluminum pipe, rising 6", stamped:

New BT:

- An 11" D. Fir bearing N44°E, 32.7 ft., scribed " T3S R33E S11 BT".

T3S R33E

S10 | S11

S15 | S14

RLS 1848

1984

Painted blazes and attached signs as per Standard Specifications for Cadastral Surveys, USFS Region 6 March, 1982. Set fence post 4 ft. north of corner.

Compass Declination: 19 1/2°E

Witness: G. Arrand.

From the intersection of USFS Rd. 5427 with 5427-090, northerly on 5427 one quarter mi. to newly barricaded road to the left. Follow said road westerly approx. 1/3 mi. to where road turns to the south. follow ridge northwesterly down hill. 200 ft. before the creek bottom go west to north-south creek. Corner is 10 ft. east of creek.

I hereby certify the above described corner monument and/or accessories was established as described on June 9, 1984.



Office of Surveyor County of Umatilla
 State of Oregon, I hereby certify that the within instrument was filed in this office
 for record on the 10th day of July, 1984
David Krumholz by Betty Cochran
 (COUNTY OFFICIAL) (DEPUTY)