

Index

File No. Z-15

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or

Survey No. _____

Cor.

No. 1/4

T 2S

R. 34E

R.D. La Grande


County Union

Merid. Willamette

N.F. Wallowa-Whitman

State Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

Found no trace of corner stone on Bts. Area has had a lot of camping and woodcutting.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

PHOTO IDENTIFICATION DATA

Photo No. EWD-17-172

Filed At. La Grande

Object Ident. Direct

Ident. By B. Barber RLS
Signature

PLANE COORDINATE POSITION DATA

State _____ Zone _____

X _____

Y _____

Estab. By _____
Agency

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Signature
Barry B. Barber

Title
P.L.S.

Division

Headquarters
Sumpter

Date
11-4-80

7100-52 (3. 68)

4
5

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

At surveyed point set 2 1/2" X 30" galvanized pipe and brass cap marked: Set pipe 25" in the ground and mound of stone around to cap.

T2S R34E
S34

1/4 

S3
OR PLS 1051

ACCESSORIES DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

From which by magnetic declination of N20°E: A 24" pine bears N39°W, 131.5 ft. scribed 1/4S34 BT. An 18" tamarac bears S45°W, 159.9 ft. scribed 1/4S3 BT. Painted blazes red and 6" red band around. Placed 54-3s, 54-4s and brass washers stamped PLS 1051 on BTs. Placed 54-2 and 54-4 on steel fence post 5' west of the corner.

Work Done By B. B. Barbour Title P.L.S. Date 11-4-80 State Registration No. OR 1051
or Agency

Certified Cor. Record Prepared? Yes No Filed At: Union County Surveyor's Date

REMARKS

Witnesses: Daniel Rowland
Doug Moser
Ron Gilroy