

OREGON CORNER RESTORATION FORM

Section 3 Township 4N Range 28E

C-13

County UMATILLA Date 11/95

CORNER DESIGNATION

W 1/4 Cor.

- Condition Report Only
- Not Found
- Renewed
- Unrecorded
- Surveyed In
- Referenced Out


Previous Renewals/Surveys, etc. ORIG. SURVEYED IN 1860 By HAFT
In 1980 Survey Krumbein Set B.C. (2 1/2") CONTRACT # 93
In place of a 5/8" Iron Rod.

Monument(s) & Accessories Found: (Condition and Source)

End Krumbein's B.C. stamped 1981
End 2 1/2" B.C. W.C. N 51° 24' E 34.66 Ft. (Stamped S 56° W 34.70)
End 2 1/2" B.C. W.C. N 42° 47' W 25.34 FT (Stamped N 46° W 25.19)

Monument Detail

Sketch



Monument Set (Procedures and Description)

AFTER Krumbein's B.C. was dug out by pipeline installation,
In its place I set a 5/8" x 30" rebar with an Alum. Cap (2")
flush with the paved surface stamped as above

SEE MY SURVEY FOR COLUCCIO

New Accessories

An Alum tag in P. Pole Bears N 39° 41' 20" E 38.52 Ft.
An Alum tag in P. Pole Bears N 48° 27' 50" W 46.26 Ft.
The NE Cor of Metal Base of STOP SIGN Bears S 57° 45' 40" W 28.15 Ft.
Punch Mk. in Highest PT. on Fire Hydrant Bears S 65° 25' E 42.94 Ft.

Location & Comments

At the Intersection of 11TH Street N-S
Nelson LN. East & McConnell LN. West
 Compass Declination _____
 Firm/Agency EDWARDS SURVEYING
 Address P.O. Box 763
HERMISTON, OR 97038
 Party Chief D. Edwards
 Notes _____
 Witness J. Coppock

Surveyor's Seal

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

D. Dennis Edwards

OREGON
 JULY 16, 1971
 G. DENNIS EDWARDS
 951

RENEWS 12/31/95

09-39-A