

OREGON CORNER RESTORATION FORM

Section 16 Township 4 NORTH Range 28 E.W.M.

L-9

County UMATILLA Date 7-13-97

CORNER DESIGNATION

T. 4N. R. 28E.

1/4
17 1/16

- Condition Report Only
- Not Found
- Renewed
- Unrecorded
- Surveyed In
- Referenced Out

Previous Renewals/Surveys, etc. THE ONLY SURVEY ADDRESSING THIS CORNER THAT WAS FOUND IN THE UMATILLA COUNTY SURVEYOR'S OFFICE WAS THE ORIGINAL G.L.O. SURVEY BY FAENEZER HAFT, CONTRACT #93, DATED SEPTEMBER 11, 1860.

Monument(s) & Accessories Found: (Condition and Source)

NO MONUMENTS OR ACCESSORIES FOUND. HAFT SET POST IN MOUND WITH TRENCH AND PITS PER INSTRUCTIONS AND DEPOSITED 1 PINT OF CHARCOAL; COUNTY ROAD NO. 1236 (QUICK RD.) NOW LIES OVER ORIGINAL CORNER LOCATION (ORIGINAL RD. # 713 SURVEYED BY GEARY KIMBRELL, MAY 23, 1911).

Monument Detail

NOT TO SCALE

Sketch

PLS
2627
1 1/2" YELLOW PLASTIC CAPS SET ON 5/8" x 30" REBARS WERE SET FOR 1/4 CORNER AND ACCESSORIES. CAPS ARE MARKED AS SHOWN AT LEFT. THE 1/4 CORNER MONUMENT WAS SET APPROXIMATELY 4" BELOW THE SURFACE OF COUNTY ROAD # 1236. ACCESSORY MONUMENTS WERE SET AS SHOWN AT RIGHT AND DESCRIBED BELOW.



Monument Set (Procedures and Description)

THE MONUMENT DESCRIBED ABOVE AT THE 1/4 CORNER WAS SET APPROXIMATELY 4\"/>

New Accessories

FOUR 5/8\"/>

FROM THE INTERSECTION OF U.S. Highway 395 AND WEST HIGHLAND EXTENSION ROAD, GO WEST APPROXIMATELY 1.1 MILES, CROSSING THE UMATILLA RIVER BRIDGE, TURN LEFT ON QUICK ROAD, AND FOLLOW THE ROAD APPROXIMATELY 0.6 MILE TO CORNER. THE CORNER IS SET IN THE CENTER OF THE ROAD AND "DO NOT DISTURB" TAGS ARE VISIBLE FROM THE ROAD AND ARE SET ON NEARBY FENCE POSTS AND A POWER POLE.

Compass Declination N/A

Firm/Agency ROBERTS

SURVEYING

Address Rt. 5 Box 5176

HERMISTON, ORE. 97838

Party Chief GARY ROBERTS

Notes WYNELL ROBERTS

Witness WYNELL ROBERTS

REGISTERED PROFESSIONAL LAND SURVEYOR

GARY R. ROBERTS
JULY 20, 1993
2627

Umatilla County Surveyor
Date 7-97
Rec'd By RR
No. 97-139-B