

OREGON CORNER RESTORATION FORM

SECTION 22 TOWNSHIP 4N RANGE 28 E

N-15

COUNTY: UMATILLA DATE 1/92

CORNER DESIGNATION

North 1/4 Corner

CONDITION REPORT ONLY  
 NOT FOUND  
 RENEWED  
 UNRECORDED  
 SURVEYED IN  
 REFERENCED OUT

PREVIOUS RENEWALS/SURVEYS, ETC.

Originally surveyed by Taft in 1860 under Contract #93. He set post in mound with trench, made pits and deposited a pint of charcoal. In 1909, Saxton of the US Reclamation Service surveyed to this corner while subdividing Section 15 and the North 1/2 of Section 22. In 1966, Ralph Thompson set a 1/4" iron pipe with a Brass Cap by single proportion using Taft's survey, not Saxton's.

MONUMENTS & ACCESSORIES FOUND: Condition and Source

Found Thompson's 1/4" iron pipe 11.79 feet West of the corner.

MONUMENT DETAIL

SKETCH

T4N R28E  
15  
1/4  
22  
1991  
LS 951

MONUMENT SET (PROCEDURES AND DESCRIPTION)

By single proportion, using Saxton's survey, I set a 2 3/8" Brass Cap on a 1" x 30" iron pipe, stamped as above, 0.3 ft. above surface. Raised mound and dug trench. Drove steel fence post with Witness sign attached, South of corner. See my County Survey #1991-2.

NEW ACCESSORIES From which


A 3/4" x 24" Bolt with 1" square nut, with Alum. tag #951, Bears N 0° 08' 56" E 10 feet.  
1 1/4" iron pipe with Brass plug Bears N 89° 27' 41" W 11.79 feet. Painted it and attached a Bearing Object sign.  
A 7/8" x 35" rebar with an Alum. tag #951 Bears S 0° 08' 56" W 10 feet.  
A 2 3/8" Brass Cap on a 1" x 30" iron pipe, stamped W.C. LS 951, 0.1 ft. above ground Bears S 89° 27' 41" E 11.79 feet. Drove steel fence post with Bearing Object and Witness signs.

LOCATION & COMMENTS

From intersection of Feedville Rd. with West R/W of RR tracks to Spokane, go Northerly 1 mile to the Corner.

SURVEYOR'S SEAL

COMPASS DEC.  
FIRM EDWARDS SURVEYING  
P.O. BOX 763, HERMISTON,  
OREGON, 97838  
PARTY CHIEF D. EDWARDS



NOTES  
WITNESS S. BENEFIT

*G. Dennis Edwards*

RECEIVED BY

Umatilla County Surveyor  
Date 4-92  
Rec'd By KF  
No. 92-45-C

