

OREGON CORNER RESTORATION FORM

SECTION 22 TOWNSHIP 4N RANGE 28 E

N-17

COUNTY: UMATILLA DATE 12/91

CORNER DESIGNATION

N E Corner

- CONDITION REPORT ONLY
- NOT FOUND
- RENEWED
- UNRECORDED
- SURVEYED IN
- REFERENCED OUT

PREVIOUS RENEWALS/SURVEYS, ETC.

Originally surveyed by Taft in 1860 under Contract #93. He set post in mound with trench, made pits and deposited a pint of charcoal.

In 1981, Krumbein set a Brass Cap in Mon. Box at the location of a RR spike. (Origin unknown.)

MONUMENTS & ACCESSORIES FOUND: Condition and Source

Found 2 1/2" Brass Cap in a monument box stamped as below.

MONUMENT DETAIL

SKETCH

T4N R28E
 15 14

 22 23
 1981
 LS 933

MONUMENT SET (PROCEDURES AND DESCRIPTION)

NEW ACCESSORIES From which

An Alum. tag #951 in Power pole Bears N 45° 23' 07" W 46.09 feet with Bearing Object sign attached.

A 3/8" x 36" Carriage Bolt Bears S 89° 24' 54" W 11.06 feet.

An Alum. tag #951 in Power pole Bears S 49° 47' 23" W 41.25 feet with Bearing Object sign attached.

A 1/2" x 36" square rebar Bears N 89° 21' 19" E 13.99 feet.

LOCATION & COMMENTS

Corner is in center-line of Hinkle Road, 430 feet South of RR crossing.

SURVEYOR'S SEAL

COMPASS DEC.
 FIRM EDWARDS SURVEYING
 P.O. BOX 763, HERMISTON,
 OREGON, 97838
 PARTY CHIEF D. EDWARDS
 NOTES
 WITNESS S. BENEFIT

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

G. Dennis Edwards

OREGON
 JULY 18, 1971
 G. DENNIS EDWARDS
 951

RECEIVED BY

Umatilla County Surveyor
 Date 4-92
 Rec'd By KK
 No. 92-45-C