

OREGON CORNER RESTORATION FORM

SECTION 21 TOWNSHIP 4N RANGE 28 E

R-11

COUNTY: UMATILLA DATE 1/92

CORNER DESIGNATION

South 1/4 Corner

CONDITION REPORT ONLY  
 NOT FOUND  
 RENEWED  
 UNRECORDED  
 SURVEYED IN  
 REFERENCED OUT

PREVIOUS RENEWALS/SURVEYS, ETC.

Originally surveyed in 1860 by Taft under Contract #93. He set post in mound with trench, made pits and deposited a pint of charcoal. In 1971 survey for C & B Livestock, Thompson set a 1" Iron rod by single proportion from wrong Sec. Cor. In 1986 survey for Swart, I set a 2 3/8" Brass Cap on a 1" x 30" Iron pipe by single proportion.

MONUMENTS & ACCESSORIES FOUND: Condition and Source

Found 2 3/8" Brass Cap on 1" Iron pipe set by me in 1986, from which a 1" Iron rod set by Thompson for the Corner Bears S 89° 02' 53" E 12.04 feet. Also found, 2 3/8" Brass Cap on a 1" Iron pipe Bears N 0° 02' 53" E 33.00 feet, stamped W.C. 33 FT. 1986 LS 951.

MONUMENT DETAIL

SKETCH

T4N R28E  
21  
1/4  
28  
1986  
LS 951

MONUMENT SET (PROCEDURES AND DESCRIPTION)

NEW ACCESSORIES From which

An Alum. tag #951 in Power pole Bears N 31° 17' 10" E 27.27 feet with Bearing Object sign attached.

An Alum. tag #951 in Power pole Bears S 13° 38' 10" E 33.58 feet with Bearing Object sign attached.

LOCATION & COMMENTS

From the intersection of Butter CR. Hwy. and Feedville Rd. go West on Feedville 0.05 mile to corner

COMPASS DEC.  
FIRM EDWARDS SURVEYING  
P.O. BOX 763, HERMISTON,  
OREGON, 97838

PARTY CHIEF D. EDWARDS

NOTES

WITNESS S. BENEFIT

SURVEYOR'S SEAL

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*G. Dennis Edwards*

OREGON  
JULY 16, 1971  
G. DENNIS EDWARDS  
951

RECEIVED BY

Umatilla County Surveyor

Date 4-92

Rec'd By RE

No. 92-45-C