

OREGON CORNER RESTORATION FORM

SECTION 23 TOWNSHIP 4N RANGE 28 E

R-17

COUNTY: UMATILLA DATE 12/91

CORNER DESIGNATION

SW Corner

CONDITION REPORT ONLY
 NOT FOUND
 RENEWED
 UNRECORDED
 SURVEYED IN
 REFERENCED OUT

PREVIOUS RENEWALS/SURVEYS, ETC.

Originally surveyed in 1860 by Taft under Contract #93. He set post in mound with trench, made pits and deposited a pint of charcoal.

MONUMENTS & ACCESSORIES FOUND: Condition and Source

At centerline of road intersection, found RR spike over 1/2" rebar. Origin unknown.

MONUMENT DETAIL

SKETCH

T4N R28E
22 23
27 26
1991
LS 951

MONUMENT SET (PROCEDURES AND DESCRIPTION)

Replaced RR spike with 2 3/8" Brass Cap on a 1" x 30" Iron pipe, stamped as above, 0.2 ft. below surface in 5" P.V.C. and in Alum. Umatilla County Monument Box. Buried RR spike and rebar inside. See my County Survey #1991-2.

NEW ACCESSORIES From which

A 1 1/2" x 32" Iron pipe, stamped 951 on rim, Bears N 48° 14' 00" E 50.84 feet.
A 2 3/8" Brass Cap on a 1" x 30" Iron pipe, stamped W.C. LS 951, Bears N 41° 49' 00" W 57.97 feet.
An Alum. tag #951 in power pole Bears S 50° 16' 00" W 42.43 feet with Bearing Object sign attached.
Center of 3" Gas Company PVC, sign #10, Bears S 38° 28' 00" E 49.20 feet.

LOCATION & COMMENTS

At intersection of Feedville Road and Hinkle Road.

SURVEYOR'S SEAL

COMPASS DEC.
FIRM EDWARDS SURVEYING
P.O. BOX 763, HERMISTON,
OREGON, 97838
PARTY CHIEF D. EDWARDS
NOTES
WITNESS S. BENEFIT

REGISTERED
PROFESSIONAL
LAND SURVEYOR

G. Dennis Edwards

OREGON
JULY 16, 1871
G. DENNIS EDWARDS
951

RECEIVED BY

Umatilla County Surveyor
Date 4-92
Rec'd By KK
No. 92-455