

OREGON CORNER RESTORATION FORM

SECTION 24 TOWNSHIP 4N RANGE 28 E

N-25

COUNTY: UMATILLA DATE 4/91

CORNER DESIGNATION

NE Corner

CONDITION REPORT ONLY
 NOT FOUND
 RENEWED
 UNRECORDED
 SURVEYED IN
 REFERENCED OUT

PREVIOUS RENEWALS/SURVEYS, ETC.

Originally surveyed in Oct. 1860 under Contract #95. W.B. Campbell set post, drove charred stake, made pits and mounds. In 1954, Higgins set 1 1/4" Iron pipe. In 1973, Krumbein set 2 1/2" Brass Cap by proportion. In 1980, Krumbein set 2 1/2" Brass Cap in place of Higgins's Iron pipe.

MONUMENTS & ACCESSORIES FOUND: Condition and Source

Found Krumbein's 1973 2 1/2" Brass Cap N 34° 41' 12" E 22.93 feet from the corner. Found Krumbein's 1980 2 1/2" Brass Cap at the corner.

MONUMENT DETAIL

SKETCH

T4N
R28E R29E
13 18

24 19
1980
RLS 933

MONUMENT SET (PROCEDURES AND DESCRIPTION)

NEW ACCESSORIES From which

An Alum. tag #951 in anchor Power pole Bears N 71° 21' 30" E 45.45 feet with Bearing Object sign attached.
The SW corner of concrete siphon box Bears N 30° 13' 20" E 35.66 feet.
The SE corner of another concrete siphon box Bears N 20° 29' 10" W 32.67 feet.
An Alum. tag #951 in Power pole Bears S 68° 46' 50" E 46.60 feet with Bearing Object sign attached.
A 5/8" rebar with Alum. tag #951 Bears S 44° 55' 35" W 46.67 feet.

LOCATION & COMMENTS

Corner is at intersection of Airport Rd. and Ott Rd.

SURVEYOR'S SEAL

COMPASS DEC.
FIRM EDWARDS SURVEYING
P.O. BOX 763, HERMISTON,
OREGON, 97838
PARTY CHIEF D. EDWARDS

NOTES

WITNESS S. BENEFIT

RECEIVED BY

Umatilla County Surveyor

Date 4-92

Rec'd By KR

No. 92-42-C

REGISTERED
PROFESSIONAL
LAND SURVEYOR

J. Dennis Edwards

OREGON
JULY 16, 1971
G. DENNIS EDWARDS
951