

OREGON CORNER RESTORATION FORM

SECTION 24 TOWNSHIP 4N RANGE 28 E

P-25

COUNTY: UMATILLA DATE 4/91

CORNER DESIGNATION

East 1/4 Corner

CONDITION REPORT ONLY  
 NOT FOUND  
 RENEWED  
 UNRECORDED  
 SURVEYED IN  
 REFERENCED OUT

PREVIOUS RENEWALS/SURVEYS, ETC.

Originally surveyed in Oct. 1860 under Contract #95. W.B. Campbell set post, drove charred stake, made pits and mounds. In 1980 Survey for County, Krumbein set 2 1/2" Brass Cap on 2" Iron pipe by single proportion.

MONUMENTS & ACCESSORIES FOUND: Condition and Source

Found Krumbein's 1980 2 1/2" Brass Cap 1 foot below surface of graveled road.

MONUMENT DETAIL

SKETCH

T4N  
R28E R29E  
  
24 . 19  
  
1980  
RLS 933

MONUMENT SET (PROCEDURES AND DESCRIPTION)

NEW ACCESSORIES From which

An Alum. tag #951 in Power pole Bears N 09° 24' 30" E 230.52 feet with Bearing Object sign attached.

A 2 3/8" Brass Cap on a 1" x 30" Iron pipe, stamped W.C. LS 951, Bears N 89° 37' 54" W 33 feet with steel post and Witness sign attached.

An Alum. tag #951 in Power pole Bears S 18° 22' 20" E 119.58 feet with Bearing Object sign attached.

A 2 3/8" Brass Cap on a 1" x 30" Iron pipe, stamped W.C. LS 951, Bears S 89° 37' 54" E 33 feet with steel post and Witness sign attached.

LOCATION & COMMENTS

From intersection of Airport Road and Ott Road, go South on Ott Rd. 1/2 mile to Corner.

SURVEYOR'S SEAL

COMPASS DEC.  
FIRM EDWARDS SURVEYING  
P.O. BOX 763, HERMISTON,  
OREGON, 97838  
PARTY CHIEF D. EDWARDS

NOTES  
WITNESSED BY

Umatilla County Surveyor

Date 4-92

Rec'd By KK

No. 92-45-c

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*G. Dennis Edwards*

OREGON  
JULY 16, 1871  
G. DENNIS EDWARDS  
951