

OREGON CORNER RESTORATION FORM

Section 21 Township 4 N Range 29 E

P-13

County UMATILLA Date 3/95

CORNER DESIGNATION

E 1/4 Cor

- Condition Report Only
- Not Found
- Renewed
- Unrecorded
- Surveyed In
- Referenced Out

Previous Renewals/Surveys, etc. ORIG SUR. DAVENPORT 1861 # 101  
He set a post in mound with charred stake

Monument(s) & Accessories Found: (Condition and Source)

NOTHING

Monument Detail

Sketch



Monument Set (Procedures and Description)

By single Proportion I set 1"X30" I. Pipe with  
2 3/8" B.C. stamped as above

SEE MY 1994-1 COUNTY PUBLIC MONUMENTATION SUR.

New Accessories

5/8" X 30" rebar with Aum Cap #951 Bears WEST 10.00 FT.

2" X 2" X 48" L Iron drive 24" Bears N0°10'48"E 1.00 FT.

1/2" X 24" rebar with Aum Cap #951 " EAST 10.00 FT.

1/4" X 33" rebar Bears S0°10' 48"W 10.00 FT.

Location & Comments

From Intersection Compass Declination \_\_\_\_\_  
of Edwards Rd & Firm/Agency EDWARDS  
Feedville Rd. Go East SURVEYING \_\_\_\_\_  
on Feedville 1 Mile Address P. Box 763  
to E. Cor Then HERMISTON, OR 97038 \_\_\_\_\_  
go 1/2 Mile North Party Chief D. EDWARDS \_\_\_\_\_  
across Fields to Cor. Notes \_\_\_\_\_  
 Witness J. COPPOCK \_\_\_\_\_

Surveyor's Seal

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*G. Dennis Edwards*

OREGON  
JULY 18, 1971  
G. DENNIS EDWARDS  
951

RENEWS 12/31/95

Umatilla County Surveyors

Date \_\_\_\_\_  
Rec'd by \_\_\_\_\_  
No. 95-608