

OREGON CORNER RESTORATION FORM

SECTION 25 TOWNSHIP 4 NORTH RANGE 29 EAST T-25

COUNTY : UMATILLA DATE 8-98

CORNER DESIGNATION

EAST 1/4

CONDITION REPORT ONLY
 NOT FOUND
 RENEWED
 UNCOVERED
 SURVEYED IN
 REFERENCED


PREVIOUS RENEWALS / SURVEYS, ETC.

ORIGINALLY SURVEYED IN 1860 BY CAMBELL UNDER CONTRACT #95. HE SET A POST IN A MOUND OF EARTH AND A CHARRED STAKE.

MONUMENTS AND ACCESSORIES FOUND: CONDITION AND SOURCE

SKETCH

MONUMENT DETAIL



MONUMENT SET (PROCEDURES AND DESCRIPTION)

BY SINGLE PROPORTION, I SET A 1" X 30" IRON PIPE WITH A 2 3/8" BRASS CAP STAMPED AS ABOVE. BRASS CAP LIES 3" ABOVE THE SURFACE.

NEW ACCESSORIES FROM WHICH

AN ALUMINUM TAG, #951 SET IN A RXR TIE FENCE POST LIES N 10'.33' E, 84.82 FEET.
A 5/8" X 30" IRON REBAR WITH PLASTIC CAP #951 LIES EAST 14.14 FEET.
AN ALUMINUM TAG, #951 ON A POWER POLE, LIES S 11'.52' E, 64.22 FEET.
A 5/8" X 30" IRON REBAR WITH PLASTIC CAP, #951, LIES N 0'.14'34" W, 38.15 FEET.

LOCATION AND COMMENTS

COMPASS DEC.

SURVEYOR'S SEAL

RECEIVED BY
Umatilla County Surveyor
Date 10-98
Rec'd By KK
No. 98-213-C

FIRM/AGENCY
EDWARDS SURVEYING
P.O. BOX 763
HERMISTON, OREGON 97838
97838

PARTY CHIEF
D. EDWARDS

NOTES

WITNESS
RICK SMITH

REGISTERED
PROFESSIONAL
LAND SURVEYOR

G. Dennis Edwards

OREGON
JULY 16, 1971
G. DENNIS EDWARDS
951
RENEWS 12/31/99