

OREGON CORNER RESTORATION FORM

Section 31 Township 4 N Range 29 E

V-3

County UMATILLA Date 3/95

CORNER DESIGNATION

N 1/4 Cor

- Condition Report Only
- Not Found
- Renewed
- Unrecorded
- Surveyed In
- Referenced Out

Previous Renewals/Surveys, etc. ORIG SUR. DAVENPORT 1861 # 101

He set a post in mound with charred stake


Krumbein Set B.C. 1973 Sur # I-21-C

Monument(s) & Accessories Found: (Condition and Source)

End 2 1/2" B.C. Stamped as below

Monument Detail

Sketch



Monument Set (Procedures and Description)

SEE MY 1994-1 COUNTY PUBLIC MONUMENTATION SUR.

New Accessories

a 1 1/2" x 3/4" rebar stamped 951 Bears S 89° 58' 34" W 10.00 FT.

a 1/2" x 24" rebar with Alum Cap " N 8 17' 08" W 10.00 FT.

a 3/4" I.D.X 27" I. Pipe stamped 951 Bears S 89° 52' 41" E 10.00 FT.

a 5/8" x 30" rebar R.Cap 951 " S 0° 05' 57" E 10.00 FT.

Location & Comments

Surveyor's Seal

From Wood ST in
Stanfield go along
Paved Rd along N
edge RR. 0.9 Mile
Then GO Northwly
on Dirt Rd 0.1 Mile
to Cor on Sly Canal
Bank.

Compass Declination _____
 Firm/Agency EDWARDS
SURVEYING
 Address P. Box 763
HERMISTON, OR 97838
 Party Chief D. EDWARDS
 Notes _____
 Witness J. COPPOCK

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

G. Dennis Edwards

OREGON
 JULY 16, 1971
 G. DENNIS EDWARDS
 951

RENEWS 12/31/95

Umatilla County Surveyor

Date

Rec'd By

No. 95-60-A