

OREGON CORNER RESTORATION FORM

SECTION 36 TOWNSHIP 4 NORTH RANGE 29 EAST X-25
COUNTY : UMATILLA DATE 8-98

CORNER DESIGNATION

EAST 1/4

CONDITION REPORT ONLY
 NOT FOUND
 RENEWED
 UNCOVERED
 SURVEYED IN
 REFERENCED

PREVIOUS RENEWALS / SURVEYS, ETC.


ORIGINALLY SURVEYED IN 1860 BY CAMBELL UNDER CONTRACT #95. HE SET A POST IN A MOUND OF EARTH AND A CHARRED STAKE.

MONUMENTS AND ACCESSORIES FOUND: CONDITION AND SOURCE

NOTHING

SKETCH

MONUMENT DETAIL



MONUMENT SET (PROCEDURES AND DESCRIPTION)

BY SINGLE PROPORTION, I SET A 1" X 30" IRON PIPE WITH A 2 3/8" BRASS CAP STAMPED AS ABOVE. BRASS CAP LIES 3" ABOVE THE SURFACE.

NEW ACCESSORIES FROM WHICH

AN ALUMINUM TAG, #951, ON A POWER POLE LIES S 12'.59' W, 109.25 FEET.
A 5/8" X 30" IRON REBAR WITH PLASTIC CAP #951 LIES S 78'.48'47" W, 233.41 FEET.
AN ALUMINUM TAG, #951, ON A POWER POLE, LIES N 5'.51'50" W, 218.94 FEET.
A 5/8" X 30" IRON REBAR WITH PLASTIC CAP, #951, LIES N 89'.52'24" E, 68.18 FEET.

LOCATION AND COMMENTS

FROM INTERSECTION OF STAGE GULCH ROAD AND LARGE POWER LINE, GO SOUTH ALONG POWER LINE 0.5 MILES TO CORNER.

COMPASS DEC.

FIRM/AGENCY
EDWARDS SURVEYING
P.O. BOX 763
HERMISTON, OREGON 97838
97838

PARTY CHIEF
D. EDWARDS

NOTES

WITNESS
RICK SMITH

SURVEYOR'S SEAL

RECEIVED BY

Umatilla County Surveyor

Date 10-98

Rec'd By KK

No. 98-213-C

REGISTERED
PROFESSIONAL
LAND SURVEYOR

G. Dennis Edwards

OREGON
JULY 16, 1971
G. DENNIS EDWARDS
951
RENEWS 12/31/99