

GPS CONTROL STATION

OREGON STATE PLANE, NORTH ZONE

STATION NAME: 4N29X5 GEODETIC COORDINATE: NAD 83(91)

SECTION: E 1/4 S31 LAT: 45°47'3.04240" N  
T. 4N., R. 29 E., W. M. LONG: 119°13'32.33604" W  
UMATILLA COUNTY  
OREGON

STATE PLANE CO-ORDINATES,  
NAD 83-91, INT. FT. :

DATE SURVEYED: March, 1998

N: 774568.367

SURVEYOR: DAVID L. HADDOCK  
PLS 852

E: 8527197.184

THETA: 0°54'13.51"

SCALE FACTOR: 0.99995230

ELEV: 588

FIRM: HADDOCK SURVEYING  
P. O. BOX 1574  
PENDLETON, OR 97801  
(541) 276-2174

ELEV. DATUM: NGVD29

HORIZONTAL ORDER: SECOND ORDER,  
CLASS I

---

LOCATION: From Wood Street in the City of Stanfield go northwest along the railroad access road on the north side of the tracks to the intersection with a driveway to the north across from the city treatment facility. Go north on this driveway approximately 300 feet. The cap is on the west side of the driveway approximately 6 feet from the road surface.

STATION: Station is a 2 1/4 inch brass disc on a galvanized iron pipe. The cap is approximately two inches above the surface of the ground.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*David L. Haddock*

OREGON  
JULY 12, 1968  
DAVID L. HADDOCK  
852

98-155-C