

OREGON CORNER RESTORATION FORM

SECTION 35 TOWNSHIP 4 NORTH RANGE 29 EAST Z-21
COUNTY : UMATILLA DATE 8-98

CORNER DESIGNATION

SE CORNER

CONDITION REPORT ONLY
 NOT FOUND
 RENEWED
 UNCOVERED
 SURVEYED IN
 REFERENCED


PREVIOUS RENEWALS / SURVEYS, ETC.

ORIGINALLY SURVEYED IN 1859 BY GATES UNDER CONTRACT #84. HE SET A POST IN A MOUND OF DIRT.

MONUMENTS AND ACCESSORIES FOUND: CONDITION AND SOURCE
NOTHING

MONUMENT DETAIL

SKETCH



MONUMENT SET (PROCEDURES AND DESCRIPTION)

BY SINGLE PROPORTION I SET A 1" X 30" IRON PIPE WITH A 2 3/8" BRASS CAP STAMPED AS ABOVE,
3" BELOW THE SURFACE. OF A GRAVELED ROAD.

NEW ACCESSORIES FROM WHICH

AN ALUMINUM TAG #951 ON A POWER POLE LIES N 43°.48'00" E, 24.75 FEET.
AN ALUMINUM TAG #951 ON A POWER POLE LIES N 82°.58'00" E, 155.95 FEET.
A 5/8" X 30" IRON REBAR WITH PLASTIC CAP #951 LIES N 0°.20'36" W, 13.90 FEET.
A 5/8" X 30" IRON REBAR AND PLASTIC CAP #951 LIES S 0°.20'36" E, 17.18 FEET.

LOCATION AND COMMENTS

COMPASS DEC.

SURVEYOR'S SEAL

FIRM/AGENCY
EDWARDS SURVEYING
P.O. BOX 763
HERMISTON, OREGON 97838
97838

PARTY CHIEF
D. EDWARDS

NOTES

WITNESS
RICK SMITH

RECEIVED BY

Umatilla County Surveyor

Date 10-98

Rec'd By KK

No. 98-213-C

REGISTERED
PROFESSIONAL
LAND SURVEYOR

G. Dennis Edwards

OREGON
JULY 16, 1971
G. DENNIS EDWARDS
951

RENEWS 12/31/99