

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 02/27/07

CORNER DESIGNATION: 4N30, E-21, The Northeast Corner of Section 11.

PREVIOUS RENEWALS/SURVEYS ETC.:

Corner was originally established by Dolphus S. Payne, under Contract No. 100, dated August 1, 1861. Notes state: Set charred stake with mound, trench, and pits as per instructions.

MONUMENT AND ACCESSORIES FOUND: None. Corner falls in farmed field about 15 feet west of a North-South fence line. A fence corner with fences East-West and South bears N 16° E, 68' +/-.

MONUMENT MARKING DETAIL:

T4N R30E
S2 | S1
S11 | S12
2007
PLS 1106

MONUMENT SET:

The fence corner NE of this corner point has existed for many years. In Survey No. 05-100-C, I accepted several fence corners as best remaining evidence of the original corner points, but those accepted fence corner locations agreed consistently with GLO record dimensions and the fence corner NE of this corner point does not. David Haddock, in his Survey No. 06-263-C did not accept the fence corner NE of this corner point, nor did he accept the old fence corner at the NW Corner of this section. I reestablish this corner point by double proportionate measure as indicated on the accompanying Record of Survey. At the reestablished corner point, I set a 2 3/8 " brass cap on 1 1/4" x 30" galvanized iron pipe with cap 14" below ground level. Monument marked as shown in monument marking detail.

New Accessories:

A 3/4" brass washer stamped "PLS 1106" 1 foot above ground level in wood fence post bears South 71° East, 17.2 feet.

A 3/4" brass washer stamped "PLS 1106" 1 foot above ground level in wood fence post bears South 24° East, 38.8 feet.

A Purple Deep-1 magnet buried 20" below ground level bears South 51° West, 32.7 feet.

A Orange Deep-1 magnet buried 20" below ground level bears North 61° West, 30.0 feet.

Attached bearing object signs to wood fence posts by brass washer accessories. Buried bearing object signs with magnets. Set steel fence post with witness sign attached 1 foot East of monument.

LOCATION AND COMMENTS: Corner is located in an actively farmed field.

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT
Micah Engum

/4N30E21

REGISTERED
PROFESSIONAL
LAND SURVEYOR
William R. Wells
OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106
RENEW 6-30-08