

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 03/16/05

CORNER DESIGNATION: 4N30J19, the North 1/4 Corner of Section 14.

**PREVIOUS RENEWALS/SURVEYS ETC.:**

Corner was originally established by Dolphus S. Payne under contract No. 100, dated August 1, 1861. Original notes state: Set charred stake, with mound, trench and pits as per instructions, for 1/4 Section Cor.

**MONUMENT AND ACCESSORIES FOUND:**

Found and accepted a fence corner with fences running North and West and a fence extending East, beginning about 500 feet East of fence corner, as best remaining evidence of original corner location.

**MONUMENT MARKING DETAIL:**

T4N R30E  
1/4 S11  
S14  
2005  
PLS 1106

**MONUMENT SET:**

At a point 6" South of fence corner, set a 2 1/2" brass cap on 1 1/4" by 30" galvanized iron pipe, 28" in the ground. Monument is marked as shown in Monument Marking Detail.

**New Accessories:**

A 5/8" x 24" iron rebar with 1 1/4" yellow plastic cap marked "OR PLS 1106 WA PLS 17372", with cap set 2" above ground in fence line bears: North 03° East a distance of 23.4 feet.  
A 5/8" x 24" iron rebar with 1 1/4" yellow plastic cap marked "OR PLS 1106 WA PLS 17372", with cap set 2" above ground in fence line bears: North 02° East a distance of 54.7 feet.  
A 5/8" x 24" iron rebar with 1 1/4" yellow plastic cap marked "OR PLS 1106 WA PLS 17372", with cap set 2" above ground in fence line bears: North 90° West a distance of 17.3 feet.  
A 5/8" x 24" iron rebar with 1 1/4" yellow plastic cap marked "OR PLS 1106 WA PLS 17372", with cap set 2" above ground in fence line bears: North 88° West a distance of 44.0 feet.

Attached "witness" sign to fence corner post North of monument. Wired bearing object signs to rebar accessories.

**LOCATION AND COMMENTS:**

Located at fence intersection West of a North-South field access road.

FIRM: William R. Wells, PLS  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

4N30J19

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*renews 6-30-06*