

# OREGON CORNER RESTORATION FORM

SECTION 24      TOWNSHIP 4 NORTH RANGE 29 EAST      N-25

COUNTY : UMATILLA      DATE 8-98

CORNER DESIGNATION

NE CORNER

CONDITION REPORT ONLY  
 NOT FOUND  
 RENEWED  
 UNCOVERED  
 SURVEYED IN  
 REFERENCED

PREVIOUS RENEWALS / SURVEYS, ETC.


ORIGINALLY SURVEYED IN 1860 BY CAMBELL UNDER CONTRACT #95. HE SET A POST IN A MOUND OF EARTH AND A CHARRED STAKE.

MONUMENTS AND ACCESSORIES FOUND: CONDITION AND SOURCE

FENCE CORNER USED BY SOME SURVEYORS. 12.5 FEET NORTH AND 26.6 FEET WEST.

SKETCH

MONUMENT DETAIL



MONUMENT SET ( PROCEDURES AND DESCRIPTION )

BY SINGLE PROPORTION, I SET A 1" X 30" IRON PIPE WITH A 2 3/8" BRASS CAP STAMPED AS ABOVE. BRASS CAP LIES 3" ABOVE THE SURFACE.

NEW ACCESSORIES FROM WHICH

A 1/2 " IRON REBAR AND PLASTIC CAP #951, LIES N 67°.40'39" E, 27.68 FEET.  
AN ALUMINUM TAG #951 IN POWER POLE LIES N 52°.32'30" E, 32.22 FET.  
A 5/8" X 30" IRON REBAR WITH PLASTIC CAP #951 LIES N 00°.02'10" E, 14.05 FEET.  
A 5/8" X 30" IRON REBAR WITH PLASTIC CAP #951 LIES **51°47'49"E 843.26 Feet**

LOCATION AND COMMENTS

FROM THE INTERSECTION OF FEEDVILLE ROAD WITH LARGE POWER LINE, GO NORTH ALONG POWER LINE 1.0 MILES. TO CORNER.

COMPASS DEC.

FIRM/AGENCY  
EDWARDS SURVEYING  
P.O. BOX 763  
HERMISTON, OREGON 97838  
97838

SURVEYOR'S SEAL

**RECEIVED BY**

Umatilla County Surveyor

Date 10-98

Rec'd By KK

No. 98-213-C

PARTY CHIEF  
D. EDWARDS

NOTES

WITNESS  
RICK SMITH

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*G. Dennis Edwards*

OREGON  
JULY 16, 1971  
G. DENNIS EDWARDS  
951  
RENEWS 12/31/99