

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 5/20/05

CORNER DESIGNATION: 4N31J-05, The Northeast Corner of Section 18.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner established by Wm. H. Odell, under Contract No. 114, Dated July 2, 1866. Record states: Set post Cor. for Secs. 7, 8, 17 & 18, on level, drove charred stake, dug pits and raised mound as per instructions.

MONUMENT AND ACCESSORIES FOUND: Field lines South and East.

**MONUMENT MARKING DETAIL:**

T4N R31E  
S7 | S8  
S18 | S17  
2005  
PLS 1106

**MONUMENT SET:**

I accepted intersection of field lines extending East and South as best remaining evidence of original corner position. At the re-established corner position, set a 2 1/2" brass cap on a 2 1/2" x 30" galvanized iron pipe with cap 20" below ground level, marked as shown in Monument Marking Detail. In setting this monument, we dug up an old rotted fence post at the accepted corner point, about 2 feet below ground.

**New accessories:**

- A silver deep-1 magnet bears North 34° East, 29.7 feet.
- A purple deep-1 magnet South 44° East, 30.4 feet.
- A blue deep-1 magnet South 34° West, 43.8 feet.
- An orange deep-1 magnet bears North 49° West, 32.3 feet.

Deep 1 magnets are buried 20" below ground line in wheat fields. Buried bearing object signs with the deep-1 magnets. Nailed "witness" sign to railroad tie post 7.5' South of monument.

LOCATION AND COMMENTS: Corner is located at a rounded field corner with field lines East and South. There a few railroad ties extending East and South of corner point.

FIRM: William R. Wells, PLS  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

/4N31J05

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*renews 6-30-06*

**RECEIVED BY**

**Umatilla County Surveyor**

Date 6-05

Rec'd By KK

No. 05-123-B