

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 02/13/07

CORNER DESIGNATION: 4N31, L-5, The West One-Quarter Corner of Section 17.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by W.H. Odell, under GLO Contract No. 114, dated July 2, 1866. Notes state: Set post corner for 1/4 section, in gulch, course N.W..

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T4N R31E  
1  
4  
S18|S17  
2007  
PLS 1106

MONUMENT SET:

Reestablished corner position by single proportionate measure between the Southwest and Northwest corners of Section 17. At reestablished corner point, set a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe, with cap 2 inches above ground level, marked as shown in Monument Marking Detail. The position for this corner was determined on Survey No. 05-123-B.

New Accessories:

A silver deep-1 magnet buried 20" in the ground bears North 45° East, 26.7 feet.  
A blue deep-1 magnet buried 20" in the ground South 30° East, 29.5 feet.  
A purple deep-1 magnet, buried 20" in the ground bears South 46° West, 30.7 feet.  
A orange deep-1 magnet, buried 20" in the ground bears North 45° West, 28.5 feet.  
Buried bearing object sign with each deep-1 magnet accessory. Set steel fence posts 2 feet East of the monument and 2 feet North of the monument with witness signs attached.

LOCATION AND COMMENTS:

Corner located in farmed field on East side of a draw. There is a old N-S field line about 43 feet West of corner. A old railroad tie "H" brace bears South 11°04' West, 200 feet.

FIRM: William R. Wells, PLS  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT  
Micah Engum

/4N31L5

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*renews 6-30-08*