

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 01/24/07

CORNER DESIGNATION: 4N31, L-9, The East One-Quarter Corner of Section 17.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by W.H. Odell, under GLO Contract No. 114, dated July 2, 1866. Notes state: Set post corner for 1/4 section, drove charred stake, dug pits, and raised mound as per instructions.

MONUMENT AND ACCESSORIES FOUND: Unique "U" shaped fence post, chunks of wood and old survey flagging in remains of old North-South fence.

MONUMENT MARKING DETAIL:

T4N R31E
1
4
S17|S16
2007
PLS 1106

MONUMENT SET:

Held slight angle point in old North-South fence line, marked with old "U" shaped fence post. Found chunks of wood and old survey flagging at corner point. At the accepted corner point, set a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe, with cap 2 inches above ground level, marked as shown in Monument Marking Detail.

New Accessories:

A 5/8" x 24" iron rebar with 1 1/4" red plastic cap stamped "OR PLS 1106, WA PLS 17372", in old fence line, bears North 26.5 feet.

A 5/8" x 24" iron rebar with 1 1/4" red plastic cap stamped "OR PLS 1106, WA PLS 17372", bears North 42° East, 25.0 feet.

A 5/8" x 24" iron rebar with 1 1/4" red plastic cap stamped "OR PLS 1106, WA PLS 17372", bears South 54° East, 33.6 feet.

A 5/8" x 24" iron rebar with 1 1/4" red plastic cap marked "OR PLS 1106 WA PLS 17372", in old fence, bears South, 35.2 feet.

Attached witness sign to old fence post West of corner. Attached bearing object signs to all rebar accessories.

LOCATION AND COMMENTS:

Corner is in a small unfarmed scab area, in a North-South draw, between farmed fields on the East and West.

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT
Micah Engum

/4N31L9

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-08