

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 05/20/05

CORNER DESIGNATION: 4N31EN01. Section corner common to Sections 18 and 19 only.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner established by David P. Thompson, under Contract No. 81, dated July 8, 1859. Record states: Set post for 1/4 Sec. Cor. and built mound of earth with pits, trench etc. as per instructions.

MONUMENT AND ACCESSORIES FOUND: 1956 photograph shows a old field line approaching from the East, into the corner area. No evidence visible evidence of this field line remains today.

MONUMENT MARKING DETAIL:

T4N
R30E R31E
S24 | S18
| S19
2005
PLS 1106

MONUMENT SET: Re-established by single proportion measurement between the West one-quarter corner of Section 19, T4N., R31E., and the position for the section corner common to Section 13 and 24, T4N., R30E., W.M. See Record of Survey filed concurrently. At re-established corner position, set a 2 1/2" brass cap on 2 1/2" x 30" galvanized iron pipe, with cap 20" below ground level, marked as shown in Monument Marking Detail.

New accessories:

A 5/8" x 24" rebar with a 1 1/4" yellow plastic cap marked "OR PLS 1106, WA PLS 17372", bears North 35° East, 63.7 feet..

A 5/8" x 24" rebar with a 1 1/4" yellow plastic cap marked "OR PLS 1106, WA PLS 17372", bears North 70° East, 39.4 feet.

A 5/8" x 24" rebar with a 1 1/4" yellow plastic cap marked "OR PLS 1106, WA PLS 17372", bears South 52° East, 46.4 feet.

A 3/4" brass washer stamped "PLS 1106, 1 foot above ground on west side of UECA pole #190902, bears South 26° East, 86.2 feet.

Attached bearing object signs to all accessories. Rebar accessories are in a North-South fence line on the East side of Terney Road.

Set a steel fence post 12.3 feet East of corner with "witness" sign attached.

LOCATION AND COMMENTS: Corner is located in wheat field, 21 feet West of centerline of Terney Road.

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

4N31N01

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Will - R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-06

RECEIVED BY

Umatilla County Surveyor

Date 6-05

Rec'd By KK

No. 05-123-B