

# OREGON CORNER RESTORATION FORM

COUNTY: Umatilla. DATE: 03/24/2010

CORNER DESIGNATION: J-13, The Northeast Corner of Section 16, Township 4 North, Range 33 East, W.M..

## PREVIOUS RENEWALS/SURVEYS ETC:

The corner was originally established by Odell and Lewis, under Contract No. 110, dated February 7, 1865. Notes state: Set post corner for Secs 9, 10, 15 & 16, drove charred stake. Dug pits & raised mound as per instructions.

In 1889, J.C. Arnold, Umatilla County Surveyor, under Survey No. 43, as recorded in Record of Private Surveys Book, stated he found the original balm post with charred end and set over the top of it a triangular basalt stone marked 3 notches on the East and 4 notches on the South.

In 1890, J.C. Arnold called the corner in his road survey for County Road No. 335.

In 1906, under Record of Survey No. 242, John Kimbrell recovered the corner but does not state what was found.

MONUMENT AND ACCESSORIES FOUND: None, falls at the end of current gravel County Road.

## MONUMENT MARKING DETAIL:

T4N R33E  
S9|S10  
S16|S15  
2010  
PLS 1106

MONUMENT SET: Held the centerline of Lembcke Road extending East and a field berm extending North and South as the best remaining evidence of the original corner position. At that point, set a 2 1/2" brass cap on a 1 1/4"x30" galvanized iron pipe with the cap buried 8" below road surface. Cap is marked as shown in "Monument Marking Detail".

### New accessories:

A silver Deep-1 magnet buried 16" below ground level in farmed field bears North 27° East, 41.6 feet.

A blue Deep-1 magnet buried 16" below ground level in farmed field bears South 31° East, 50.0 feet.

A pink Deep-1 magnet buried 16" below ground level in farmed field bears South 28° West, 48.3 feet.

A 5/8"x24" iron rebar with a 1 1/4" red plastic cap marked "OR PLS 1106 WA PLS 17372" 16" below ground level in farmed field bears South 90° West, 60.00 feet.

Buried bearing object signs with all Deep-1 magnets. Attached witness sign to railroad tie fence post 13.7 feet North of monument.

LOCATION AND COMMENTS: Corner is located at the end of Lembcke road with a field berm extending North and a fainter field berm extending South. There is a old railroad tie fence post with old fence remains just North of corner.

FIRM: Wells Surveying  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT  
Dean Roy  
4N33J13

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*renews 6-30-10*