

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla. DATE: 10/02/18.

CORNER DESIGNATION: J-9, The Southeast corner of Section 8, Township 4 North, Range 33 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC: Corner was originally established by Odell and Lewis, Deputy Surveyors, under Contract No. 110, dated February 7, 1865. Notes state:

Set post corner for Secs. 8, 9, 16 & 17. Drove charred stake. Dug pits and raised mound as per instructions.

MONUMENT AND ACCESSORIES FOUND: None. Reestablished corner point at the intersection of field berms extending North-South and West. There is an old bent steel fence post 1/2 foot South of corner point.

MONUMENT MARKING DETAIL:

T4N R33E
S8 | S9

S17 | S16
2018
PLS 1106

MONUMENT SET: Set a 2 3/8" brass cap on 1 1/4" galvanized iron pipe 30" in the ground. Cap marked as shown in Monument Marking Detail.

New accessories:

- A silver Deep 1 magnet bears N 06° E, 14.3'.
- A blue Deep 1 magnet bears S 01° W, 16.1'.
- A orange Deep 1 magnet bears N 84° W, 19.0'.
- A 5/8" by 24" rebar with red plastic cap bears N 27° W, 13.0'.


Red plastic cap is marked "ORPLS 1106 W/APLS 17372". All rebar accessories have "bearing object" signs wired to them. Deep 1 magnets are buried 15" below ground line and a "bearing object" sign is buried beside the Deep 1 magnets.

Attached "Witness" sign to old steel fence post 1/2' South of corner.

LOCATION AND COMMENTS: Corner is located at the intersection of old field berms extending North-South and West.

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

Surveyor's Seal



Will. R. Wells
Renews 6-30-20

RECEIVED BY
Umatilla County Surveyor
Date: 10/11/2018
Recd By: TMA
No.: 18-087-R

IAN33J-9